

THE CONTENTS OF THIS  
DOCUMENT ARE THE HIGHEST  
QUALITY OBTAINABLE

INITIAL *nm* DATE *3/26/91*



Report No. WM-F1-81-003, Rev. 3

Date: July, 1985

## INTERNAL TECHNICAL REPORT

Title: A HISTORY OF THE RADIOACTIVE WASTE  
MANAGEMENT COMPLEX AT THE IDAHO  
NATIONAL ENGINEERING LABORATORY

Organization: WASTE MANAGEMENT PROGRAMS DIVISION  
RMC OPERATIONS BRANCH

Author: Revised July, 1985

Checked By:

A. D. Rodgers 8/5/85  
A. D. Rodgers, Manager  
RMC Operations Branch

Approved By:

J. H. Nelson  
J. H. Nelson, Deputy Manager  
Waste Management Programs Division

THIS DOCUMENT HAS  RECEIVED PATENT  
CLEARANCE 

WM-F1-81-003, Rev. 3  
July 1985

A HISTORY OF THE  
RADIOACTIVE WASTE MANAGEMENT COMPLEX  
AT THE  
IDAHO NATIONAL ENGINEERING LABORATORY

Waste Programs Division,  
RWMC Operations Branch

Revised July 1985

Issued by WIPD Document Control

*Licky Johnson 8-30-85*

## CONTENTS

1.	INTRODUCTION .....	1
2.	EARLY DISPOSAL PRACTICES (1952-59) .....	14
2.1	Waste Disposal Site Selection .....	14
2.2	Early Environmental Monitoring .....	15
2.3	Geology and Hydrology of the Burial Ground .....	17
2.4	First Trench Burials .....	17
2.5	Disposal Procedures .....	19
2.6	Disposal of Rocky Flats Waste .....	23
2.7	Burial Ground Expansion .....	24
2.8	First Pit Disposals .....	24
3.	INTERIM BURIAL GROUND (1960-63) .....	29
3.1	Interim Burial Ground Program Policies and Procedures ....	29
3.2	Transfer of Burial Ground Operations .....	31
3.2.1	Standard Practice .....	31
3.2.2	TRU Waste Disposal .....	32
3.3	Incidents at the NRTS .....	32
3.3.1	SL-1 Accident .....	32
3.3.2	1962 Flood .....	34
3.4	Environmental Monitoring .....	36
4.	WASTE BURIAL .....	37
4.1	Environmental Concern .....	37
4.1.1	Environmental Studies .....	37
4.1.2	Cessation of TRU Waste Burial .....	39
4.1.3	Investigation of Alternative Sites .....	39
4.2	Changes in Disposal Procedures and Facilities .....	40
4.2.1	1966 Fires .....	40
4.2.2	1969 Flooding .....	41
4.3	Environmental Monitoring .....	41
4.3.1	Monitoring at the Perimeter .....	41
4.3.2	Subsurface Water Monitoring .....	43

5.	WASTE MANAGEMENT (1970-84)	44
5.1	Segregation of TRU Waste	44
5.1.1	Temporary Aboveground Storage	44
5.1.2	Transuranic Storage Area (TSA) Pad 1	45
5.1.3	Transuranic Disposal Area (TDA)	51
5.1.4	TSA-2	52
5.1.5	TSA-3	60
5.1.6	TSA-R	61
5.1.7	Intermediate-Level Transuranic Storage Facility (ILTSF)	62
5.2	Receipt of Offsite TRU and Low-Level Waste	65
5.3	Retrieval of Waste	67
5.3.1	ACC Retrieval Study	68
5.3.2	Initial Drum Retrieval Project	68
5.3.3	Early Waste Retrieval Project	70
5.3.4	TSA Reentry Study	72
5.4	Changes in Waste Management Practices	73
5.4.1	Waste Information Systems	73
5.4.2	Waste Storage Practices	73
5.4.3	Space Utilization	74
5.4.4	Liquid Corrosive Chemical Disposal Area	84
5.4.5	Drainage	87
5.4.6	Flood Control	88
5.4.7	Radiation Exposure Reduction	88
5.4.8	Fire Protection and Emergency Action Plans	89
5.4.9	Environmental Surveillance Since 1970	92
5.4.10	Criticality Control	103
6.	SUMMARY OF CURRENT RWMC FACILITIES AND PRACTICES	104
6.1	Site	104
6.1.1	SDA	104
6.1.2	TSA	104
6.2	Support Facilities	108
6.3	Administration of the RWMC	109
7.	REFERENCES	115
	APPENDIX A--AREA AND FACILITY TERMINOLOGY CHANGES AND ACRONYM LISTING	A-1
	APPENDIX B--CONVERSION FACTORS	A-7

## FIGURES

1.	Location of Burial Ground (RWMC) at INEL .....	16
2.	High-radiation-level waste disposal in 1950s .....	20
3.	Dumping of boxes containing routine waste, 1950s .....	22
4.	Plan of NRTS Burial Ground .....	25
5.	Hand stacking of drums, 1950s .....	27
6.	Concrete survey monument marking trench location .....	28
7.	Dumping of drums (1963-69) .....	33
8.	1962 "Chinook"-caused flood at Burial Ground .....	35
9.	1969 "Chinook"-caused flood at Burial Ground .....	42
10.	Transuranic Storage Area overview .....	47
11.	TDA pad before it was covered with soil .....	48
12.	TDA penetration exposing 208-litre drums .....	53
13.	TSA-1, TSA-2, and ASWS, SWEPP, and C&S ASWS .....	54
13.a	C&S Building equipment air lock .....	55
13.b	Container Assay System .....	56
13.c	Real-Time Radiography .....	57
13.d	Container Integrity System .....	58
14.	Waste stack in ASWS-2 on TSA Pad 2 .....	59
14.a	TSA Active Storage Areas .....	63
15.	Covering of the TSA-R pad .....	64
16.	Free-air transfer to ILTSF vaults .....	66
17.	EWR operations inside the OAC .....	71
18.	New storage grid system used in ASWS-2 on TSA Pad 2 .....	75
19.	New storage grid system used on TSAR Pad .....	76
20.	NRTS 45.4-metric ton baler .....	80
21.	Current pit disposal .....	82

21.a	Digging 45.7-cm soil vault .....	82a
22.	Rock ripper removing fractured basalt in Pit 16 .....	85
23.	Aggregate pile resulting from FY 1980 explosive fracture .....	86
24.	Concrete shield for radiation exposure .....	90
25.	Bottom-discharge cask .....	91
26.	Flame testing of fire-retardant paint .....	93
27.	RWMC air-monitoring locations .....	101
28.	TLD locations .....	101
29.	Aerial photograph of the RWMC (Spring 1984) .....	105
30.	Layout of the RWMC .....	106
31.	Flow chart of solid waste disposition at the RWMC .....	107
32.	WMF-611, RWMC Guardhouse .....	110
33.	RWMC Documentation Tree .....	112

#### TABLES

1.	History of burial ground administration .....	2
2.	Burial ground developments and facility additions .....	5
3.	Opening and closing dates of pits and trenches .....	18
4.	Pad opening and closing dates .....	49
5.	Solid radioactive waste disposed of or stored at the RWMC from 1952 through 1984 .....	77
6.	Summary of RWMC monitoring .....	99

A HISTORY OF THE  
RADIOACTIVE WASTE MANAGEMENT COMPLEX  
AT THE  
IDAHO NATIONAL ENGINEERING LABORATORY

1. INTRODUCTION

The Radioactive Waste Management Complex (RWMC) is located within the Idaho National Engineering Laboratory (INEL), formerly the National Reactor Testing Station (NRTS). The INEL covers 2315.5 km<sup>2</sup> of semiarid land in southeastern Idaho near the center of the eastern Snake River Plain. The U.S. Atomic Energy Commission (AEC), now the U.S. Department of Energy (DOE), established the NRTS in 1949 as a site for building and testing various types of nuclear facilities.

Major waste management developments, decisions, and practices at the RWMC after the site was selected fall into the following time periods: early disposal (1952-59), interim burial ground (1960-63), mid-to-late 60s (1964-69), and 1970-to date. These periods are presented as the major sections of this report. Appendix A contains a listing of terminology changes and an explanation of acronyms used throughout the report. Appendix B is a listing of conversion factors.

Information for this report was drawn primarily from existing records and reports. Available information on the earliest years was somewhat limited since much of the documentation concerning operation at the RWMC before 1970 was destroyed when the required retention period had been exceeded. Table 1 presents a chronological listing of the changes in waste management responsibilities of the government and contractor. Table 2 summarizes the known RWMC developments and facility additions by year.



TABLE 1. HISTORY OF BURIAL GROUND ADMINISTRATION

Year	ID	Contractor
1952	Health Physics Division Site Survey Branch was responsible for operation of Burial Ground and environmental monitoring. Idaho Operations Office (ID) division of Engineering and Construction (ID-E&C) drew up burial plot plans.	National Industrial Maintenance Co. (NIMCO) was responsible for excavation, unloading, and burial work and Central Facilities maintenance (1949-53).  E. B. Steele Co. was responsible for surveying.
Fall 1953		Lost River Transportation Co. was responsible for Central Facilities maintenance.
1953-1966 Energy		Phillips Petroleum Co. (PPCo) Atomic Division was responsible for Central Facilities maintenance and Idaho
Chemical E&C.		Processing Plant (ICPP); absorbed ID-
1953	Health and Safety Division (ID-H&S) was formed from ID Health Physics Safety Branch and Fire Department. Site Survey Branch still was responsible for Burial Ground and onsite radioactive waste disposal.	F. C. Torkelson Co. was responsible for surveying and architectural engineer contract for Site.
1960-1963 AEC.		PPCo became waste-receiving agent for
1961		PPCo assumed responsibility for health physics supervision at Burial Ground.
1962 Ground.	AEC-ID was responsible for Burial Ground management.	PPCo Health and Safety was responsible for operation of Burial
1962		PPCo Nuclear Safety Committee was responsible for nuclear safety rules.

TABLE 1. (continued)

Year	ID	Contractor
1966		Idaho Nuclear Corporation (INC) (formed as a joint subsidiary of Aerojet-General Co. and Allied Chemical Corporation) was responsible for Burial Ground. Absorbed F. C. Torkelson Co., as INC Architect-Engineering Branch. CPP-HP made receiving agent for offsite waste.
1967	ID-H&S was reorganized into ID Health Services Laboratory (ID-HSL) and ID Operational Safety and Technical Support (ID-OSTS) Division; Environmental Branch of ID-HSL was responsible for technical direction of solid waste burial. Hazards Control Branch of ID-OSTS was responsible for health and safety surveillance.	
1969		INC reorganized; PPCo became a part owner. Nuclear and Operational Safety (NOS) Division (combined H&S Branch, Operations Surveillance Branch, and Nuclear Safety Committee) was responsible for independent internal review of burial operations.
1970	Waste Management Branch was formed in Nuclear Technology Division (NT-ID) and assumed responsibility for Burial Ground management.	NOS was responsible for all INC waste management and pollution control. In late 1970, that responsibility was transferred to Chemical Programs Division.

TABLE 1. (continued)

Year	ID	Contractor
1971 services		Aerojet Nuclear Co. (ANC) became contractor for operating the RWMC. Technical operation of the RWMC was transferred from Aerojet Safety Division to Waste Management Programs to ensure independent auditing capability.
1975	Energy Research and Development Administration (ERDA) replaced the AEC and assumed responsibility for radioactive waste management at the INEL.	
1976		EG&G Idaho, Inc., (EG&G) replaced ANC as INEL prime contractor.
1977	Department of Energy (DOE) replaced ERDA and assumed responsibility for radioactive waste management at the INEL.	

TABLE 2. BURIAL GROUND DEVELOPMENTS AND FACILITY ADDITIONS

Year	Facilities and Equipment Installed	Major Developments
1952	--	Original 5.2 ha of Burial Ground fenced
1954	--	Rocky flats waste shipped to RWMC Transuranic waste from Rocky Flats received visual survey <i>Ground cover placed over filled trenches periodically</i>
1957	--	Burial Ground expanded to 35.2 ha Pit disposal begun to accommodate large and bulky waste TRU waste placed in separate pits
1958	--	NRTS flood control project constructed on Big Lost River, adjacent to Burial Ground--including diversion dam and spreading areas
1960	--	HSL established ten monitoring holes drilled to the basalt adjacent to waste-filled excavations
1960-63	--	Procedures for acceptance of shipments and standardized forms adopted
1962	--	System of dikes and ditches constructed around Burial Ground Diversion dike for Big Lost River constructed by diking spreading area HP technician assigned duty to guide operation, witness disposal, and sign records showing disposal made
1963	--	Began random dumping of Rocky Flats waste in pits instead of stacking.

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1966	--	<p>Minimum soil cover over buried waste increased from 0.6 to 0.9 m</p> <p>Minimum trench depth increased from 0.9 to 1.5 m</p> <p>Heavy metal plate used for compaction</p> <p>Fire protection improved</p> <p>Waste covering at end of week required</p>
1969	--	<p>Extensive dike system constructed to protect Burial Ground from runoff in local drainage basin</p> <p>Temporary grading and diking provided inside Burial Ground to control internal drainage</p> <p>Stacking of waste from Rocky Flats reinstituted</p>
1970	--	<p>RWMC expanded to 57.6 ha when 22.4-ha TSA was added</p> <p>Burial of TRU waste discontinued; TRU waste stored aboveground on asphalt, then covered with layers of plywood, plastic, and soil</p> <p>Diking around SDA completed</p> <p>At least 0.6 m of soil placed over bedrock at bottom of new pits and trenches</p>
1971	<p>Burial Ground trailer</p> <p>TSA change trailer</p> <p>Forklift truck, backhoe, and crane</p>	<p>RWMC land graded to provide major drainage channels for surface water</p> <p>Waste carried by ATMX cars, improved rail shipment carriers</p> <p>Stacking mechanized with hydraulic-cylinder unloader</p> <p>Computerized Waste Management Information System implemented</p> <p>Fire Protection Plan instituted</p> <p>Equipment and personnel permanently assigned to the RWMC</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1972	<p>Dozer/scrapper to cover Rocky Flats waste on ITSA pad</p> <p>Second access road for emergency use to west end of the RWM</p>	<p>Waterproofing of ITSA pad upgraded</p> <p>ITSA pad extended 76.2 m</p> <p>Upgrading of containers initiated, i.e., new steel drums painted white</p> <p>TDA pad established for surface disposal of waste with less than 10 nCi/g of transuranic nuclides</p> <p><u>Emergency Action Plan completed</u></p>
1973	Mobile yard ramp and four forklift trucks	<p>Training program for operators and supervisors at Burial Ground initiated</p> <p>TRU combustible and noncombustible waste packaged separately</p> <p><u>Environmental Surveillance Plan</u> formulated</p> <p>Sampling of small mammals and soil outside SDA begun</p> <p>Measuring of temperature and humidity in ITSA storage configuration implemented</p> <p>Drainage of RWM upgraded</p> <p>Machine compression test on ten 208.2-L steel drums performed</p> <p>Burial Ground subsurface water monitoring plan begun</p>
1974	<p>BORAX V building for storage of Waste Management material</p> <p>ITSA exclusion fence</p> <p>WMF-601</p> <p>WMF-602 Decontamination Facility South</p> <p>Decontamination Facility evaporation pond fenced</p>	<p>Two 18 925-L water storage tanks installed under ground for fire-protection purposes</p> <p>Plywood boxes covered with fiberglass-reinforced polyester (FRP), and steel drums lined with 0.23-mm polyethylene liners</p> <p>Initial Drum Retrieval (IDR) Program begun (1974-78)</p> <p>Most onsite waste transported in plastic bags for compaction</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1974 (cont)	<p>Hydraulic, bale-type compactor installed in Equipment and Compactor Building for volume reduction of waste before disposal</p> <p>Perimeter electrical monitoring power around RWMC and evacuation alarm system installed</p> <p>Railroad spur to TSA completed providing direct shipment of waste to RWMC</p> <p>Air support structure placed over IOR</p> <p>Second TSA storage pad</p>	<p>Bioassay program initiated</p> <p>Radiation survey of grounds mechanized</p> <p>Computerized Transuranic-Contaminated Waste Container Information System (TCWCIS) developed and implemented</p>
1975	<p>TSA air-support weather shield (ASWS)</p> <p>TSA intrusion alarm system</p> <p>362.9-kq-capacity front-end loader and hydraulic excavator</p> <p>TSA-2 pad extended</p> <p>TDA pad (Pad A) extended</p>	<p>Metal corrosion coupons placed with stored waste in TSA</p> <p>Soil level raised above SDA pits and trenches to exclude moisture accumulation (1975, 1976, 1978)</p>
1976	<p>Intermediate-Level Transuranic Storage Facility</p> <p>WVF-603 water storage tank and pumphouse</p> <p>Air-support weather shield for EWR project</p> <p>TSA-R pad constructed and placed in operation</p> <p>SDA sump pump installed</p> <p>Movable Operating Area Confinement (OAC), including change booths, fire protection equipment, and air moving and filtering equipment used for retrieval in ASWS for EWR</p>	<p>Early Waste Retrieval project started</p> <p>Flora and fauna studies started</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1976 (cont)	Cherry picker Excavator 59-metric ton crane Front-end loader Water spray trailer Two flatbed trailers One air compressor	
1977	WWF-504 RMMC change and lunch facility  Soil vaults  Standby electrical power  TSA pad sweeper Dump truck Ten-wheel flat bed truck Earth tamper Water spray trailer Air compressor (breathing type)	Cell monitoring instruments installed to measure temperature and humidity in TSA-1
1978	7570-L water truck 40.8 metric ton crane Earth scrapers Rough-terrain forklift  Additional vaults for ILTSF	Operating procedures standardized  Offsite and onsite packaging criteria standardized and issued to replace Letters of Agreement with waste generators  Training guidelines and evaluation program established  Health physics monitoring program improved  Site characterization instrumentation program improved  Core sampling for subsurface studies of 1972-78 initiated and continued  Flora and fauna studies of 1977-78 improved  Air monitoring of 1974-78 improved  Additional soil stabilization and moisture exclusion initiated (0.6 to 0.9 m of soil cover over previously buried TRU waste)  Fire testing of FRP boxes



TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1979	<p>Twenty 61-cm-dia. ILTSF vaults; five 40.6-cm-dia. ILTSF vaults</p> <p>Radiation Analysis Laboratory (RAL) in WMF-601</p> <p>Heavy Equipment Storage Shed (HESS), WMF-609</p> <p>ILTSF pad area expanded</p> <p>Dozer with ripper</p>	<p>Bottom-discharge Cask Design Guidelines issued</p> <p>Removal of basalt in disposal area initiated to increase disposal space</p> <p>Fire testing of FRP boxes, plywood boxes, and metal boxes</p>
1980	<p>Discrete sumps and drainage facilities on TSA-2</p> <p>Fifteen 61-cm-dia. and five 40.6-cm-dia. ILTSF vaults</p> <p>New fire pumps and piping systems in WMF-603</p> <p>1.3-m soil vault sleeve</p> <p>Firehose cart with 304.8 m of reeled hose</p> <p>Two 11.5-m<sup>3</sup> dump trucks</p> <p>Front-end loader</p> <p>ASWS block-lifting fixture</p> <p>55.95-W turbine pump to replace original RWMC deep-well pump</p>	<p>Testing of explosive fracturing of basalt in SDA--scale-model tests outside RWMC and in Pit 17</p> <p>Conceptual designs and estimates completed on large (54.4-metric ton) bottom-discharge cask</p> <p>Relocation of Air Support Weather Shield to Cell 3, TSA-2</p> <p>Disposal of PNL-E low-level waste commenced</p>
1981	<p>Dry-pipe fire mains to TSA and SDA; and fire sprinkler systems in WMF-602, -603, and -609</p>	<p>First production-scale explosive rock fracturing; 2977 m<sup>3</sup> of basalt fractured and removed from Pit 17.</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1981 (cont)	<p>Ultraviolet (fire) detection system installed in ASWS-2 and around Pit 16</p> <p>Guardhouse (WMF-611) under construction</p> <p>Production deep well pump installation and testing completed</p> <p>Five, 40.6-cm-diameter and twenty-two 61-cm-diameter ILTSF vaults installed with shield plugs and radiation-monitoring tubes</p> <p>Cylindrical concrete monuments to replace damaged old-style monuments</p> <p>Liquid Corrosive Chemical Disposal Area (LCCDA) closed</p> <p>Weighing lysimeter data logger and weather station installed and tested</p> <p>Water storage tank interior sandblasted and repainted</p> <p>127-metric ton Manitowoc crawler-mounted crane</p> <p>ASWS-3 deflated and stored</p>	<p>Fire-retardant paint testing</p> <p>Thermal testing of ILTSF vaults</p> <p>Water removed from ILTSF vaults before drying and resealing the vaults</p> <p>SDA acid pit sampled; presence of waste radionuclides or other toxins not indicated by analyses of soil samples</p> <p>Monitoring potentially flammable gas in TSA cells</p> <p>TRU waste shipments stacked in designated sections on ASWS-2</p>
1982	<p>Motion-detection system installed in ASWS-2</p> <p>Guardhouse (WMF-611) completed</p> <p>Decontamination Facility South (DFS) (WMF-602) decontaminated and decommissioned then redesignated Operational Support Facility (OSF)</p> <p>Radiography room and equipment installed in OSF for examination of drums and boxes of waste (a Waste Experimental Reduction Facility (WERF) project)</p>	<p>PWMIS, YCWIS, and SWIMS converted to NOMAD VP/CSS data base management system</p> <p>PWMC flooded by rapid snowmelt</p> <p>Flood-control upgrade</p> <p>Explosive rock-fracturing; 14 196.1 m<sup>3</sup> of basalt fractured and removed from Pit 17; 22 950 m<sup>3</sup> of basalt fractured in second FY 1982 blasting but not removed at end of FY 1982</p> <p>Hydrogen explosion testing (mock-up, 203.2-L waste drums)</p> <p>Thermal testing of ILTSF vaults</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1982 (cont)	<p>Twenty-two, 61-cm-diameter and ten, 40.6-cm-diameter ILTSF vaults installed; twelve, 121.9-cm-diameter ILTSF vaults procured for NWCF filters</p> <p>Rotary snow-blower</p> <p>7.3-metric ton, rough-terrain, extendable-boom, LOED forklift</p> <p>5.4-metric ton forklift</p> <p>1.8-metric ton forklift</p> <p>11.5-m<sup>3</sup>, heavy-duty dump truck</p> <p>49.9-metric ton, bottom-discharge cask</p>	<p>New definition of TRU-contaminated material</p> <p>Soil sampling to detect trace elements or organics that could be transported by air to beyond the RWMC boundary</p> <p>Russian thistle samples</p> <p>Rock-fracturing tests using BRI-STAR and freezing water</p>
1983	<p>14 11.5-m<sup>3</sup> dump truck</p> <p>White 29.9-metric ton truck tractor</p> <p>Hyster 2722-Kg forklift</p> <p>Toyota 1814-Kg forklift</p> <p>Konler 50 Kw generator set</p> <p>Jeep dolly</p> <p>2-Trailers, 36-metric ton, flat deck</p> <p>2-Trailers, 32-metric ton, folding deck</p> <p>Light generator trailer</p> <p>Four 40.6-cm-diameter, twenty 61-cm-diameter and twelve 121.9-cm-diameter ILTSF vaults installed</p>	<p>Explosive rock-fracturing; 22,950 m<sup>3</sup> of basalt fractured in pots 18 and 19</p> <p>Offsite and onsite packaging criteria were reviewed and combined into two DOE-10 documents</p> <p>Quality Assurance Program Plans were prepared by each waste generator and approved for TRU waste shipments to the RWMC</p> <p>New drain culvers from north SDA external drain channel to main RWMC external drain channel installed. Explosive rock fracturing in main drain channel between RWMC and Adams Blvd. completed</p> <p>Environmental assessments performed for wind gaps dikes 1 and 2 raised approximately six feet</p>

TABLE 2. (continued)

Year	Facilities and Equipment Installed	Major Developments
1983 (cont)	Visitor parking lot paved, exterior to Guard Post, WMF-611  New TSA/SWEPP access bridge installed  TSA-3 asphalt pad installed	
1984 thru July 1985	Soil vacuum, truck mounted  2 trailers, 36-metric ton, flat deck  Railcar mover  SWEPP, 2.7 metric ton forklift (LP)  Radiation Analysis Lab decommissioned  SWEPP and C&S buildings completed  The two south bays of the HESS enclosed  WVRF compactor filtered exhaust system modified to discharge outside the building  Bulk disposal crane pad constructed  SWEPP Scales (2268Kg)	Explosive rock-fracturing; 24,092 m <sup>3</sup> of basalt fractured in pits 19 and 20. The broken rock was placed as rip-rap on flood control dike number-1 and 2 (July 1, 1984).  RWMC Spill/Decon Plan approved  Automated TRU Waste Interim Tracking System developed and implemented  Spreading Area Flood Control Dike No. 1 raised six feet, and Dike No. 2 eight feet  Productivity measurement system implemented and automated  SWEPP operational August 1, 1985    Geotextile use in pit floor implemented

## 2. EARLY DISPOSAL PRACTICES (1952-59)

### 2.1 Waste Disposal Site Selection

The AEC recognized the need to develop a local disposal ground for the solid, radioactively contaminated waste that would be generated during the operation of nuclear reactors and associated facilities at the National Reactor Testing Station. The United States Geological Survey (USGS) was consulted in the selection of a disposal site on the NRTS. The disposal site was selected in 1951 according to the following criteria:<sup>1,2</sup>

- a. An area of not less than 4 ha
- b. Accessibility without extensive road construction
- c. An area with not less than 4.6 and preferably 6.1 m of unconsolidated sedimentary overburden on the bedrock. (At that time the personnel selecting the site believed that trenches would be 3.7 to 4.6 m deep and that waste materials would be covered with at least 1.8 m of soil.)
- d. Appreciable amounts of clay in the burial sediments, especially in the beds below a depth of 3.7 m. A USGS letter<sup>1</sup> stated that there should be at least several feet of sediment under the buried material to slow the downward percolation of gravitational water and to assist natural absorption of radioactive solids dissolved in circulating water. The letter stated that appreciable amounts of clay in the sediments would facilitate natural absorption.
- e. Overburden sufficiently cohesive to stand a short period in vertical or nearly vertical walls

- f. An area not directly up the groundwater stream from existing or potential reactor sites or other places where water production wells may be drilled.
- g. Good surface drainage, leading away from existing or potential installations or water production sites.

A 40.0-ha area, located in the southwestern corner of the NRTS and characterized by fine-grained sediments deposited by the Big Lost River, was proposed for disposal operations. In May 1952, a 5.2-ha tract of this area was established as the NRTS Burial Ground for solid waste disposal.<sup>3,4</sup> At that time, AEC was also considering the area as a disposal site for solid waste generated at nuclear facilities in other parts of the country.<sup>5</sup> The Burial Ground site is located in Section 18, T2N, R29E, 3.2 km southwest of the Experimental Breeder Reactor-I (EBR-I) site, 8.1 km west of the Central Facilities Area, and 25.7 km southeast of Arco (see Figure 1).

## 2.2 Early Environmental Monitoring

Before the introduction of any radioactive material at the NRTS, extensive detailed information had been obtained between 1949 and 1950 on the natural background radiation. This environmental appraisal included evaluations of the effects of naturally occurring radionuclides in air, water, soil, and vegetation, and on predominant wildlife. The study established a base line against which quantities of radionuclides originating from reactor operations could be recognized easily and appraised.<sup>6</sup>

From the beginning of waste disposal, portable instruments had been used for direct monitoring, visual inspections, and surveys of the excavation areas. Although no routine air samples were taken in connection with the Burial Ground, an air-monitoring network throughout the NRTS and offsite had been maintained by AEC ID-HSL since the NRTS was first established by AEC-ID.<sup>7</sup>




Figure 1. Location of Burial Ground (RWMC) at INEL.

### 2.3 Geology and Hydrology of the Burial Ground

During 1952, the USGS performed an investigation of the geology and hydrology of the larger 40.0-ha area.<sup>3,5</sup> A USGS report, published in 1953,<sup>5</sup> stated that the area was generally favorable for the disposal of limited quantities of short-lived radioactive waste and that its sediments would have greater ion-exchange capacity than sediments nearer the Big Lost River. The report noted that surficial sediment was more than 2.7 m thick over much of the site. AEC approved the site location since it met most of the original criteria for a suitable burial site.<sup>3</sup>

The 1953 USGS report also suggested that water in contact with contaminated material might carry contaminants downward to the water table. However, contamination was thought unlikely since percolating water would be subject to ion-exchange processes, and local precipitation would contribute little recharge water.

### 2.4 First Trench Burials

On July 8, 1952, the first trench was opened for the disposal of mixed-fission-product (MFP) waste generated at the NRTS. The MFP waste consisted mainly of contaminated paper, laboratory glassware, filters, and metal pipe fittings.<sup>3</sup> Although the Burial ground was designated for disposal of solid waste, one report<sup>5</sup> states that certain liquids in sealed containers were placed in the first trench.

Between 1952 and 1957, Trenches 1 through 10 were excavated to basalt.<sup>8,9,10</sup> These early trenches were approximately the same size, averaging 1.8 m wide, 274.3 m long and 3.7 m deep.<sup>9</sup> Spacing between these trenches ranged from 3.4 m up to 18.3 m.<sup>10</sup> Table 3 lists the opening and closing dates of trenches at the Burial Ground.

The Burial Ground was enclosed almost immediately with a barbed wire fence. Metal tags placed on the fence served as the sighting devices to mark trench locations.



TABLE 3. OPENING AND CLOSING DATES OF PITS AND TRENCHES<sup>10</sup>

<u>Trench Number</u>	<u>Date Opened</u>	<u>Date Closed</u>	<u>Trench Number</u>	<u>Date Opened</u>	<u>Date Closed</u>
1	07-08-52	10-01-54	40	10-07-65	01-13-66
2	10-01-54	12-21-54	41	01-04-66	10-04-66
3	12-22-54	04-22-55	42	05-09-66	01-16-67
4	04-22-55	11-21-55	43	10-20-66	06-01-67
5	11-04-55	03-29-56	44	01-13-67	03-24-67
					6
					03-22-56
					09-04-56
					45
					02-28-67
					09-27-67
7	08-14-56	12-20-56	46	09-25-67	03-14-68
8	12-13-56	05-07-57	47	02-28-68	08-05-68
9	01-17-57	09-06-57	48	08-08-68	05-02-69
10	07-19-57	02-07-58	49	11-18-68	06-30-69
11	02-11-58	07-25-58	50	07-01-69	11-01-69
12	01-03-58	01-16-59	51	10-30-69	04-08-70
13	01-09-58	04-24-59	52	03-04-70	07-04-70
14	04-16-59	07-30-59	53	07-01-70	10-12-70
15	07-31-59	10-16-59	54	09-23-70	05-04-71
16	10-17-59	04-12-60	55 <sup>a</sup>	04-07-71	03-12-82
17	11-01-59	07-01-60	56	12-29-71	02-01-73
18	05-10-60	07-20-60	57	12-28-72	06-11-74
19	07-05-60	11-29-60	58	02-20-74	08-17-81
20	12-01-60	06-30-61			
21	12-13-60	01-10-61	<u>Pit Number</u>		
22	02-01-61	04-25-61	1	11-01-57	10-01-59
23	06-20-61	09-15-61	2	10-01-59	07-01-63
24	10-01-61	07-31-62	3	12-15-61	01-03-63
25	08-01-61	07-27-62	4	01-03-63	09-26-67
26	04-13-62	08-17-62	5	06-18-63	12-22-66
27	08-20-62	01-04-63	6	05-18-67	10-22-68
28	12-26-62	03-12-63	7	09-19-66	10-05-68
29	11-19-62	03-20-63	8	03-06-67	11-00-69
30	03-02-63	09-12-63	9	11-08-67	06-09-69
31	03-25-63	11-22-63	Acid Pit	01-01-54	01-01-61
32	04-01-63	11-18-63	10	08-07-68	07-08-71
33	10-11-63	08-11-64	11	04-14-70	10-16-70
34	03-18-64	08-27-64	12	07-02-70	09-12-72
35	08-28-64	01-19-65	12	07-20-71	07-29-74
36	12-01-64	07-24-65	14	07-01-74	03-31-76
37	12-24-64	07-01-65	15	06-25-75	07-05-84
38	05-15-65	09-16-65	16	05-22-68	Still open
39	07-20-65	11-05-65	17	08-20-82	Still open

a. Trench 55 was closed administratively 03-12-82 due to unknown conditions at the east end of the trench.