Waste Area Group (WAG) 10

Ordnance Interim Action

Cost Estimate for Alternatives 2, 3, and 4

Prepared jointly by EG&G Idaho and MK-Ferguson of Idaho Company

for the U.S. Department of Energy Idaho Operation Office 785 DOE Place Idaho Falls, ID 83402-1562

Remedial Design and Action Costs for Alternative 2

The remedial design and action costs for Alternative 2 are presented in the proposed plan and address control through the use of administrative barriers. The methodology used to estimate the costs is described below.

- Design costs are based on estimated number of drawings and historical experience.
- Vendor estimates were used for the cost of materials.
- Installation costs were taken from other similar estimates prepared for the clean-up action at the Idaho National Engineering Laboratory (INEL).

Specific details related to the cost estimate for Alternative 2 are provided in the following tables:

Table 1 Remedial Design Cost Estimate

Table 2 Remedial Action Cost Estimate

Table 1

Remedial Design Cost Estimate

(\$ by category)

Activity	Engineering	Technical Support	<u>Total</u>
Title II Design	\$ <u>6,400</u>	\$ <u>9,200</u>	\$ <u>15,600</u>
Totals	\$6,400	\$9,200	\$15,600

ţ

Table 2

Remedial Action Cost Estimate

ALTERNATE 2	Cost
Materials/Installation Fencing (new 15,000 ft) Fencing (Repair 60,000 ft) Signs Labor Subtotal Materials/Installation	\$46,000 14,000 9,000 <u>42,000</u> 111,000
Labor Supervision	56,000
TOTAL REMEDIAL ACTION ALTERNATIVE 2	\$167,000.

Remedial Design and Action Costs for Alternative 3

The remedial design and action costs for Alternative 3 are presented in the proposed plan and address remediation by detonation and incineration. The methodology used to estimate the costs is described below.

- Design costs are based on estimated number of drawings and historical experience.
- Vendor estimates were used for the cost of materials.
- Installation costs were taken from other similar estimates prepared for the clean-up action at the Idaho National Engineering Laboratory (INEL).

Specific details related to the cost estimate for Alternative 3 are provided in the following tables:

- Table 3 Remedial Design Cost Estimate
- Table 4 Remedial Action Cost Estimate

Table 3

Remedial Design Cost Estimate

(\$ by category)

Activity	Engineering	Technical <u>Support</u>	<u>Total</u>
Record Search Safety Analysis Title II Design	\$170,000 85,000 <u>40,000</u>	\$30,000 35,000 <u>20,000</u>	\$200,000 120,000 _60,000
Totals	\$295,000	\$85,000	\$380,000

5

Table 4

Remedial Action Cost Estimate

ALTERNATE 3	Cost
Ordnance Search Supervisor/Tech. Support Labor Equipment (Geophysical/Electomag Survey) Subtotal Ordnance Search	\$144,000 272,000 <u>154,700</u> 570,700
Ordnance Detonation Supervisor/Tech. Support (800 hrs.) Labor (2400 hrs) Equipment 1-T Truck (Rental) Crane (Rental)	64,000 103,200 26,560 53,120
FEL (Rental) Subtotal Ordnance Detonation	<u>53,120</u> 300,000
Materials	30,000
Soil Samples	450,000
Soil Remediation Excavate 185 cy (\$75/cy) Transport 185 cy (\$100/cy) Incinerate 185 cy (\$3,225/cy) Subtotal Soil Remediation	13,875 18,500 <u>596,625</u> 629,000
TOTAL REMEDIAL ACTION ALTERNATIVE 3	\$1,979,700

المعران الأثارة المعتراء

Remedial Design and Action Costs for Alternative 4

The remedial design and action costs for Alternative 4 are presented in the proposed plan and address remediation by detonation and composting. The methodology used to estimate the costs is described below.

- Design costs are based on estimated number of drawings and historical experience.
- Vendor estimates were used for the cost of materials.
- Installation costs were taken from other similar estimates prepared for the clean-up action at the Idaho National Engineering Laboratory (INEL).

Specific details related to the cost estimate for Alternative 4 are provided in the following tables:

• Table 5 Remedial Design Cost Estimate

Table 6 Remedial Action Cost Estimate

Table 5

Remedial Design Cost Estimate

(\$ by category)

Activity	Technical Engineering	Support	<u>Total</u>
Record Search Safety Analysis Title II Design	\$170,000 85,000 <u>80,000</u>	\$ 30,000 35,000 <u>40,000</u>	\$200,000 120,000 <u>120,000</u>
Totals	\$385,000	\$105,000	\$440,000

t

11.4

Table 6 Remedial Action Cost Estimate

ALTERNATIVE 4	<u>Cost</u>
Ordnance Search Supervisor/Tech. Support Labor Equipment (Geophysical/Electomag Survey) Subtotal Ordnance Search	\$144,000 272,000 <u>154,700</u> 570,700
Ordnance Detonation Supervisor/Tech. Support (800 hrs.) Labor (2400 hrs) Equipment 1-T Truck (Rental) Crane (Rental) FEL (Rental) Subtotal Ordnance Detonation	64,000 103,200 26,560 53,120 <u>53,120</u> 300,000
Materials	30,000
Soil Samples 450 Samples @ \$1,000 per şample Confirmation Sampling (50 samples @ \$500) Subtotal Samples	450,000 _25,000 475,000
Composting Operation Pilot Plant Excavate 185 cy (\$75/cy) Transport 185 cy (\$10/cy) Bioremediation 185 cy (\$850/cy) Site Reclamation Subtotal Composting Operation	77,025 13,875 1,850 157,250 10,000 260,000
TOTAL REMEDIAL ACTION ALTERNATE 4	\$1,635,700