

# Field Sampling Plan for Groundwater Monitoring Under Operable Unit 10-08 for Fiscal Years 2002, 2003, and 2004

T. J. Haney April 2002

Idaho National Engineering and Environmental Laboratory Bechtel BWXT Idaho, LLC

# Field Sampling Plan for Groundwater Monitoring Under Operable Unit 10-08 for Fiscal Years 2002, 2003, and 2004

T. J. Haney

April 2002

Idaho National Engineering and Environmental Laboratory Environmental Restoration Program Idaho Falls, Idaho 83415

Prepared for the
U.S. Department of Energy
Assistant Secretary for Environmental Management
Under DOE Idaho Operations Office
Contract DE-AC07-99ID13727

# Field Sampling Plan for Groundwater Monitoring Under Operable Unit 10-08 for Fiscal Years 2002, 2003, and 2004

INEEL/EXT-01-01529

April 2002

Approved by	
so.wh.	4/10/02
Stephen G. Wilkinson, Project Manager	Date
_	
THE resurre	4/18/02
Douglas H. Preussner, Project Engineer	Date

# **ABSTRACT**

The purpose of this document is to direct the field sampling team in sampling efforts to support the OU 10-08 remedial investigation and to describe the number, type, and location of samples and the types of analyses. Information from this investigation will expand the baseline of groundwater information that will be used to develop a plan for future sitewide groundwater monitoring.



# **CONTENTS**

ABS	TRAC	CT	iii
ACR	ONYN	MS	viii
1.	INTI	RODUCTION	1-1
	1.1	Scope	1-1
	1.2	Idaho National Engineering and Environmental Laboratory Back	kground1-1
	1.3	Existing Data.	1-1
		1.3.1 Identification of Data Gaps	1-1
2.	DAT	TA USES	2-1
	2.1	Data Quality Objectives	2-1
	2.2	Action Levels	2-1
3.	SAM	MPLING LOCATION, FREQUENCY, AND MEDIA	3-1
4.	SAN	MPLE IDENTIFICATION	4-1
5.	SAN	MPLING EQUIPMENT AND PROCEDURES	5-1
	5.1	Sample Collection	5-1
		5.1.1 Site Preparation	5-1
		5.1.2 Field Measurements	
6.	SAN	MPLE HANDLING, PACKAGING, AND SHIPPING	
	6.1	Field Screening	6-1
	6.2	Sample Shipping	6-1
7.	DOG	CUMENTATION	7-1
	7.1	Field Documentation	7-1
	7.2	Project Organization and Responsibility	7-2
8.	WAS	ASTE MINIMIZATION	
9.	HAN	NDLING AND DISPOSITION OF INVESTIGATION DERIVED	WASTE9-1
10.		ALITY	

	10.1	Quality	Control Sampling 10	-1
		10.1.1	Performance Evaluation Samples	-1
	10.2	Quality	Assurance Objectives	) <b>-</b> 1
		10.2.1 10.2.2 10.2.3 10.2.4 10.2.5 10.2.6	Precision and Accuracy 10 Minimum Detection Limits 10 Critical Samples 10 Representativeness 10 Comparability 10 Completeness 10	)-2 )-2 )-2 )-2
11.	DAT	A VALIE	DATION, REDUCTION, AND REPORTING11	1
12.	REF	ERENCE	S	!-1
Appe	ndix A	-Figure	es Showing the Monitoring Well Locations	
Appe	ndix B	—Sampl	ing and Analysis Plan Tables	
			FIGURES	
1-1.	Map	of the IN	EEL Site showing the locations of major facilities	l <b>-</b> 2
			TABLES	
2-1.	OU 1	.0-08 <b>CO</b>	PCs and required quantitation levels	2-2
5-1.	Speci	ific well i	nformation	5-2
5-2.	Speci	ific groun	ndwater sample requirements for routine monitoring.	5-5

## **ACRONYMS**

AEC Atomic Energy Commission

ARDC Administrative Record and Document Control

ASTM American Society for Testing Materials

BBWI Bechtel BWXT Idaho LLC

CERCLA Comprehensive Environmental Response, Compensation, and Liability Act

CFR Code of Federal Regulations

CLP Contract Laboratory Program

CO Consent Order

COC chain of custody

COPC contaminant of potential concern

cpm counts per minute

DAR Document Action Request

D&D&D deactivation, decontamination, and decommissioning

DOE Department of Energy

DOE-ID Department of Energy Idaho Operations Office

DOT Department of Transportation

DQO data quality objective

EPA Environmental Protection Agency

ER Environmental Restoration

FFA Federal Facility Agreement

FFA/CO Federal Facility Agreement/Consent Order

FSP Field Sampling Plan

FTL field team leader

GC gas chromatograph

GFP gas flow proportional counting

gpm gallons per minute

HASP Health and Safety Plan

HCl hydrochloric

HDPE high-density polyethylene

HRS Hazard Ranking System

ID identification

IDEQ Idaho Department of Environmental Quality

IDW investigation-derived waste

IH industrial hygienist

INEEL Idaho National Engineering and Environmental Laboratory

LSC liquid scintillation counting

MCL maximum contaminant level

MCP management control procedure

MS matrix spike

MSD matrix spike duplicate

NCP National Contingency Plan

NPL National Priorities List

O&MM Operating and Maintenance Manual

ORP oxidation reduction potential

OU operable unit

PE performance evaluation

PM project manager

PPE personal protective equipment

PQL practical quantitation limit/level

QA quality assurance

QAPjP Quality Assurance Project Plan

QC quality control

RCRA Resource Conservation and Recovery Act

RCT radiological control technician

RDX cyclotrimethylene trinitroamine

RI/FS remedial investigation/feasibility study

RML Radiation Measurements Laboratory

ROD Record of Decision

RWP radiological work permit

SAP Sampling and Analysis Plan

SDA Subsurface Disposal Area

SDG Sample Delivery Group

SMO Sample Management Office

SOP standard operating procedure

SOW Statement of Work

TBP tributyl phosphate

TNT trinitrotoluene

TPR technical procedure

TRU transuranic

TSA Transuranic Storage Area

USGS United States Geological Survey

VOA volatile-organic analysis

VOC volatile organic compound

WAG waste area group

WERF Waste Experimental Reduction Facility

WDDF Waste Determination and Disposition Form

WGS Waste Generator Services

# Field Sampling Plan for Groundwater Monitoring under Operable Unit 10-08 for Fiscal Years 2002, 2003, and 2004

### 1. INTRODUCTION

# 1.1 Scope

The work described in this Field Sampling Plan (FSP) supports the Operable Unit (OU) 10-08 Waste Area Group (WAG) 10 remedial investigation/feasibility study (RI/FS) investigation under the Federal Facilities Agreement and Consent Order (FFA/CO) at the Idaho National Engineering and Environmental Laboratory (INEEL). The goals of the project are discussed in the RI/FS Work Plan (DOE-ID 2001b).

The Sampling and Analysis Plan (SAP) consists of two parts: this FSP and the *Quality Assurance Project Plan (QAPjP) for WAGs 1, 2, 3, 4, 5, 6, 7, and 10* (DOE-ID 2001). This FSP has been prepared in accordance with INEEL Environmental Restoration (ER) management control procedures (MCPs) and guidance from the U.S. Environmental Protection Agency (EPA) document, *Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA* (EPA 1988). This FSP describes the field activities that will occur and the QAPjP describes the processes and programs that ensure the data generated will be suitable for its intended use.

The purpose of this FSP is to guide the field team in the collection of groundwater samples on a regular, defined schedule from a limited number of boundary, guard, and baseline wells in fiscal years 2002, 2003, and 2004. The objectives of this investigation are discussed in detail in the WAG 10, OU-10-08 RI/FS Work Plan (DOE-ID 2002).

# 1.2 Idaho National Engineering and Environmental Laboratory Background

Located 42 mi west of Idaho Falls, Idaho, the INEEL occupies 890 mi<sup>2</sup> of the northwestern portion of the Eastern Snake River Plain (Figure 1-1). Comprehensive INEEL historical and geological information relevant to the INEEL is provided in the WAG 10, OU 10-08 RI/FS Work Plan (DOE-ID 2002).

# 1.3 Existing Data

The United States Geological Survey (USGS) has performed numerous environmental studies and investigations in and around the INEEL. Data from USGS wells and from USGS samples collected at OU 10-08 wells will be used along with the data generated during ER groundwater sampling activities. Additional discussion is available in the OU 10-08 RI/FS Work Plan (DOE-ID 2002).

#### 1.3.1 Identification of Data Gaps

The USGS and others have studied the hydrogeology of the INEEL for over 40 years. Groundwater studies specific to various facilities have been conducted since 1971. The OU 10-08 RI/FS Work Plan (DOE-ID 2002) provides a discussion of known and suspected contaminant sources and the plan to identify data gaps pertaining to groundwater.




Figure 1-1. Map of the INEEL Site showing the locations of major facilities.

### 2. DATA USES

# 2.1 Data Quality Objectives

The data quality objectives (DQOs) for the OU 10-08 groundwater sampling are contained in the RI/FS Work Plan (DOE-ID 2002).

During the DQO scooping process, the original directions and assumptions identified for OU 10-08 in the OU 10-04 Work Plan (DOE-ID 1999) are still considered valid. These directions and assumptions are: 1) Historical groundwater data would be consolidated and reviewed to eliminate the need for collecting new data to the extent practicable. 2) The groundwater data previously obtained for other site activities are of sufficient quality to support the OU 10-08 RI/FS decision process.

#### 2.2 Action Levels

The contaminants of potential concern (COPCs) and action levels are listed in Table 2-1. The sampling and analysis plan (SAP) table, included as Appendix B of this document, shows the wells to be sampled and the laboratory analyses for each sample.

Table 2-1. OU 10-08 COPCs and required quantitation levels.

Contaminant Type	Contaminant Name	Action Level and/or MCLs°	PQL Required (At least 1/2 MCL)	Analytical Method
Organics:	Carbon Tetrachloride	0.005 mg/L	$0.001~\mathrm{mg/L^d}$	All via USEPA
(Volatile organic	cis-1,2-Dichloroethene (cis-1,2-DCE)	$0.07~\mathrm{mg/L}$	$0.01~\mathrm{mg/L}^\mathrm{d}$	
compounds)	Methylene Chloride (Dichloromethane)	0.005 mg/L	$0.001~\mathrm{mg/L^d}$	Method 8260-B
	Tetrachloroethylene (PCE)	0.005  mg/L	$0.001~\mathrm{mg/L^d}$	
	Trans-1,2-Dichloroethene (trans-1,2-DCE)	0.1 mg/L	$0.001~\mathrm{mg/L^d}$	Appendix IX Group
	Trichloroethene (TCE)	$0.005~\mathrm{mg/L}$	$0.001~\mathrm{mg/L^d}$	
Inorganics:	Arsenic (As)	0.05  mg/L	0.01 mg/L	e
(Metals)	Beryllium (Be)	0.004  mg/L	$0.0008~\mathrm{mg/L}$	e
	Cadmium (Cd)	0.005  mg/L	$0.001 \mathrm{mg/L}$	e
	Chromium (Cr)	0.1 mg/L (total)	0.01 mg/L	e
	Lead (Pb)	Action Level = $0.015 \text{ mg/L}$	$0.003~\mathrm{mg/L}$	e
	Mercury (Hg)	0.002 mg/L	$0.0002~\mathrm{mg/L}$	e
	Zinc	5 mg/L (SDWS[5])	0.020  mg/L	e
Other:	Nitrate (as Nitrogen)	10  mg/L	2 mg/L	ac
	$TNT^a$	$0.1~{ m mg/L}^{ m j}$	0.05  mg/L	USEPA Method 8330
	$RDX^{\phi}$	$0.03~{ m mg/L}^{ m j}$	0.015  mg/L	USEPA Method 8330
Radionuclides:	Gross Alpha	15 pCi/L - Total	4 pCi/L	GFP
	Gross Beta	Not to exceed 4 mrem/yr effective dose equivalent	4 pCi/L	GFP
	Gamma emitters	15 pCi/L - Total	3 pCi/L	Gamma Spec.
	Uranium (U) and daughters	0.030 mg/L - Total		USEPA Method 908.0, 908.1
	Iodine-129 (I-129)	1 pCi/L	0.1 pCi/L	LSC

Table 2-1. (continued)

-				
Analytical Method	GFP	GFP; LSC	rsc	
ed (CL)	9	g	Τ	
PQL Required (At least 1/2 MCL)	1 pCi/L	10 pCi/L	400 pCi/L	
Action Level and/or MCLs <sup>c</sup>	8 pCi/L	900 pCi/L	20,000 pCi/L	
<i>β</i> an	∞	006	20,000	
Contaminant Name	Strontium-90 (Sr-90)	Fechnetium-99 (Tc-99)	Tritium (H-3)	
)e	Stror	Tech	Triti	
Contaminant Type	Radionuclides: (continued)			

a. TNT = trinitrotoluene

b. RDX = royal demolition explosive

c. MCL = Maximum contaminant level.

d. Practical quantification limit/level (PQL) based on 25 mL sample volume.

e. Via USEPA Document No. EPA-600/4-79-020 and/or EPA-600/R-04/111 Methods in conjunction with INEEL ER-SOW-156 specifications for Sample Delivery Group (SDG) Type 1C data.

f. Via Standard Method Part 4500 F (Method C, D, or E) of USEPA Method 300.0 Revision 2.1), 340.1, 340.2, or 340.3 in conjunction with INEEL ER-SOW-156 specifications for SDG Type-3 data.

g. Via American Society for Testing and Materials (ASTM) Standard Method D 3867-90 (Method A or B), Standard Method Part 4500- NO3 (Method D, E, F), or USEPA Method 300.0 (Revision 2.1) or 353.2 (Revisions 2.0), in conjunction with INEEL ER-SOW-156 specifications for SDG Type-3 data.

h. GFP = Gas flow proportional counting.

i. LSC = Liquid scintillation counting.

j. Based on "1 in 10,000" Risk-based action levels from the EPA Integrated Risk Information Service.

Notes in italics (i.e., TNT and RDX) are analyses required by the OU 10-04 Record of Decision. TNT and RDX will be collected from well Highway 3 only.

# 3. SAMPLING LOCATION, FREQUENCY, AND MEDIA

The general categories of wells identified for sampling under this FSP include:

- Downgradient boundary wells
- Downgradient guard wells
- Upgradient baseline wells

These general categories of wells have been listed in order of sampling priority. The downgradient boundary wells and guard wells are considered the most important to fill data gaps. The project will provide the field team with the necessary guidance to ensure the proper wells are sampled. The wells are presented in Table 5-1. The groundwater monitoring wells will be sampled at least annually as presented in the Work Plan (DOE-ID 2002) for the analyses shown in the Appendix B "Sampling and Analysis Plan Tables." Figures A-1 through A-3 in Appendix A show the locations of the monitoring wells to be sampled.

# 4. SAMPLE IDENTIFICATION

A systematic 10-character sample identification code will be used to uniquely identify all samples. The uniqueness of the number is required for maintaining consistency and ensuring that no two samples are assigned the same identification code. In addition, the sample identification code identifies the WAG conducting the sampling, the sample type, if the sample is a duplicate, and the code's two-letter suffix (analysis code) can be used to identify the requested analysis for each sample. The Sample Management Office (SMO) assigns the sample numbers. The Integrated and Environment Data Management System is used to ensure the uniqueness of sample identification.

#### 5. SAMPLING EQUIPMENT AND PROCEDURES

Sample collection is discussed in Section 5.1. The groundwater monitoring wells, listed in Table 5-1, will be sampled for the analyses shown in the Appendix B SAP table. When possible, sampling will be coordinated with USGS personnel.

## 5.1 Sample Collection

## 5.1.1 Site Preparation

All required documentation and safety equipment will be assembled at the well sampling site, including, radios, fire extinguishers, personal protective equipment (PPE), bottles and accessories.

Before sampling, all sampling personnel are responsible for having read both the SAP and the corresponding HASP (INEEL 2002). The field team leader (FTL) will perform a daily site briefing to discuss potential hazards and ensure that all personnel have the required training. The FTL will assign a team member to maintain document control and note this appointment in the WAG 10 groundwater sample logbook per MCP-231 (Logbooks for ER and D&D&D Projects).

All sampling equipment that comes in contact with the sample media will be cleaned following Technical Procedure (TPR)-6541, "Decontaminating Sampling Equipment." The exception to this will be dedicated submersible sampling pumps. Sampling manifolds will be either decontaminated prior to bringing them to the field or decontaminated following use in each well before using them on another well.

#### 5.1.2 Field Measurements

Initially, the field team will establish the work control zone as indicated in the HASP (INEEL 2002), don the appropriate PPE, and measure the depth to water. The water level data are used to determine the volume of water that must be purged before sampling. The field team will measure water levels at each well before purging using either an electronic measuring device or a steel tape measure. A post-sampling water level measurement is not required. In addition to the water level measurement, the field team will also measure the height from the depth-to-water measuring point to the top of the well casing and the stickup of the well casing either above the ground surface or the well pad. Field procedures for measuring water levels in wells are included in TPR-6566, "Measuring Groundwater Levels."

Table 5-1 shows the primary wells that will be sampled. The project will supply the field team with the necessary well completion data, and the field team will calculate the purge volume based on the current water level and will record all calculations on the well purging data form. The project will supply the field team with the approximate past purge volume as a crosscheck.

An inline flow meter may be attached to the sampling apparatus before purging to provide an accurate indicator of the pumping rate. If used, the portable inline flow meter will be attached "downstream" of the sampling port, so decontamination of the flow meter assembly between wells does not occur. The pre-purge flow meter reading will be recorded on the well purging data form so that the total volume purged can be recorded upon sample completion. If an inline flow meter is not used, then the purge water flow volume will be measured using a measured bucket and a watch to measure the approximate flow rate. This will measure the amount of time it takes to fill a specific volume of the bucket (ex: one or five gallons).

mation	HIGHTOIL.
for	5
٠,=	=
_	-
_	i
1170	>
منابند	3
S	2
-	-
v	5
٩	2
7	5
۲	3

Well ID	Primary Wells	Screened Interval <sup>a</sup>	$\operatorname{Northing}^{lat}$	Easting <sup>b</sup>	Depth to Bottom (ft)	Approx. Depth to Water
	Boundary Wells					
450	USGS-001	600 <b>B</b> 630	650509.14	335610.808	635.7	588
458	0SGS-009	620B650	654491.92	258101.051	654.1	209
535	08GS-086	Open	667053.21	243371.419	691	649
550	USGS-101	750B865	686264.547	374809.428	865	771
552	USGS-103	Open	652206.339	295938.213	160	583
554	USGS-105	Open	651355.361	277395.306	800	029
557	USGS-108	Open	650807.007	285611.423	092	609
558	USGS-109	600 <b>B</b> 800	651255.188	265735.781	800	621
559	USGS-110	580B780	652325.738	321866.503	780	566
183	HIGHWAY 2	741B786	687427.66	411631.14	786	725
	Guard Wells					
184	HIGHWAY 3	680B750	687065.16	277159.41	750	538
451	USGS-002	675B696	688843.68	352631.521	704	629
553	USGS-104	550B700 Open hole	662584.669	295915.137	560	555
555	USGS-106	605B760 Open hole	669059.406	280993.981	760	584
556	USGS-107	270B690 Open hole	667130.881	307797.235	069	477

_	٠
(bettin	77777
Conti	3
`	_
_	
V	)
٥	2
Tahl	2003

Well ID	Primary Wells	Screened Interval <sup>a</sup>	Northing <sup>b</sup>	Easting <sup>b</sup>	Depth to Bottom (ft)	Approx. Depth to Water
	Baseline Wells					
453	USGS-004	285B315 Perforated	771126.166	419184.76	553	251
		322B553 Open hole				
457	USGS-008	782B812	678015.33	226141.02	812	992
468	01SGS-019	639B705	756882.924	288826.869	401	276
474	USGS-025	285B320	812272.22	347254.46	320	272
475	USGS-026	232B267	803222.19	369554.53	266.5	212
476	USGS-027	250B260 Perforated	782870.402	401830.07	312	228
		298B308 Perforated				
147	DH-1B	380 Open	767163.757	320726.773	400	268
250	P&W-3	322B401	818797.24	350802.53	406	304
a. All in feet	a. All in feet below land surface.					
b. Northings	b. Northings and eastings are North American Datum 27.	ın Datum 27.				

### 5.1.3 Well Purging

For the purposes of this document, it is assumed that each monitoring well has a operating dedicated pump. The field team will use TPR-6570, "Sampling Groundwater," and specific well information to calculate purge volumes. Waste management is discussed in Section 9.

During the purging operation, the field team will use the Hydrolab (DataSonde® or MiniSonde®) or an equivalent instrument to measure the purge water for specific conductance, pH, dissolved oxygen, and temperature. If the system allows for measurement of oxidation reduction potential (ORP), then that data will also be collected. The field team will complete a functional check on the Hydrolab (or equivalent instrument) per instructions in the manufacturers manual. If there are extremes in temperature, the FTL may determine that a functional check should be performed more frequently. The factory-provided operating manual will be followed when using the Hydrolab DataSonde, MiniSonde, or equivalent system.

Per TPR-6570, the field team will collect initial readings for specific conductance, pH, dissolved oxygen, temperature, and flow rate just after purging begins and at regular intervals thereafter. All Hydrolab (or equivalent instrument) readings will be recorded on the well purging data form. The flow rate will be recorded in the WAG 10 groundwater sample logbook. There is also space on this form to record readings for total dissolved solids (65% of the conductivity reading). The water parameter readings will provide a check on the stability of the water sampled over time.

Following purging and collection of field measurements in compliance with TPR-6570, groundwater samples will be collected. Table 5-2 outlines the specific requirements for containers, preservation methods, sample volumes, and holding times for these analyses. Special requirements for volatile organics are included in TPR-6570. The samples collected for metals analysis will be filtered during sample collection. The preferred order for water sample collection is covered in TPR-6570.

Table 5-2. Specific groundwater sample requirements for routine monitoring.

	Cc	ontainer		
Analytical Parameter	Size	Type	Preservative	Holding Time <sup>a</sup>
Volatile organics (VOA°) (SW-846-8260B)	40 mL	3 glass vials w/teflon septa	4°C and H <sub>2</sub> SO <sub>4</sub> to pH <2	14 days
2,4,6-trinitrotoluene (TNT)	1 L	Amber glass	Cool 4°C	В
Cyclonite (RDX)	1 L	Amber glass	Cool 4°C	В
Total Metals—filtered CLP list	1 L	G or P <sup>d</sup>	$pH < 2$ , $HNO_3$	6 months, Hg 28 days
Nitrate (as nitrogen)	500 mL	G or P	None	48 hours
Tritium (H-3)	125 mL	1 HDPE	None	6 months
Gamma spectroscopy analysis	1 – 2 L	1 – 2 HDPE	$pH < 2, HNO_3$	6 months
Gross alpha/beta; Sr-90; Am-241	3 L	3 HDPE or 1 cubitainer	$pH < 2, HNO_3$	6 months
Tc-99	1 L	HDPE	HNO <sub>3</sub> to pH <2	6 months
I-129	1 L	Amber glass or HDPE	None	28 days <sup>e</sup> 180 days <sup>f</sup>

a. Holding times are from date of collection as referred to in Federal Register Vol. 49, No. 209, October 26, 1984.

Aqueous organics: need to collect one sample in triplicate volume for each analysis.

b. Collection to extraction: 7 days. Extraction to analysis: 40 days.

c. VOA = Volatile organic analysis.

d. G or P = Glass or plastic.

e. 28 days in high-density polyethylene (HDPE).

f. 180 days in amber glass.

### 6. SAMPLE HANDLING, PACKAGING, AND SHIPPING

After groundwater samples are collected from the well, the gloved sampling technician wipes the bottles to remove residual water and places them in the custody of the designated sample custodian. The sample custodian/shipper is responsible for ensuring that clear tape is placed over bottle labels, lids are checked for tightness, parafilm (excluding VOA samples) is placed around lids, and samples are bagged and properly packaged before shipment. Additional information is found in MCP-244, "Chain of Custody, Sample Handling, and Packaging for CERCLA Activities."

# 6.1 Field Screening

Groundwater samples have been collected periodically from INEEL wells for several decades. The laboratory results from all of these samples show that the samples are orders of magnitude below the Department of Transportation (DOT) classification of radioactive material. Based on the process knowledge from the previous monitoring results and the fact that all samples are collected from wells outside the facility fences, neither a field sample radiation screen nor a laboratory shipping screen will be required for these groundwater samples.

# 6.2 Sample Shipping

Samples will be transported in accordance with the regulations issued by the DOT (49 Code of Federal Regulations [CFR] Parts 171 through 178) and EPA sample handling, packaging, and shipping methods (40 CFR 261.C.3C.3). Additional information is found in MCP-244. All samples will be packaged and transported to protect the integrity of the sample and prevent sample leakage.

Upon receipt, laboratory personnel will check the temperature of each batch of coolers per their contract. The laboratory will communicate these temperatures to field personnel, and to the project through SMO, to ensure adequate coolant is used to cool the samples during shipment (if cooling is required). In addition, the laboratory will communicate any other discrepancies, such as broken samples or loss of chain-of-custody, to the project through the SMO. The project will determine the appropriate corrective action case-by-case.

#### 7. DOCUMENTATION

The elements of sample documentation covered in this section are covered in additional detail in the *Quality Assurance Project Plan (QAPjP) for WAGs 1, 2, 3, 4, 5, 6, 7, and 10* (DOE-ID 2001). The FTL or designee is responsible for controlling and maintaining all field documents and records and for ensuring that all required documents are submitted to the Administrative Record and Document Control (ARDC) coordinator.

Field changes requiring document revision will be implemented by the FTL in accordance with the latest revision of MCP-135, "Creating, Modifying, and Canceling Procedures and Other DMCS-Controlled Documents." All entries will be made in permanent, nonsmearable black ink. All errors will be corrected by drawing a single line through the error and entering the correct information. All corrections will be initialed and dated. However, the nature of sampling activities is such that small variations from the FSP are occasionally required to complete the task. These small deviations in the procedures are a one-time event for which a document action request (DAR) is not necessary or desirable. These variations will be recorded in the WAG 10 groundwater sample logbook.

The serial number or identification (ID) number and disposition of all controlled documents (e.g., chain-of-custody [COC] forms) will be recorded in ARDC's document control logbook. If a document is lost, a new document will be completed. The loss of a document and an explanation of how the loss was rectified will be recorded in the document control logbook. The serial number and disposition of all damaged or destroyed field documents will also be recorded. All voided and completed documents will be maintained in a project file until completion of the sampling events, at which time all logbooks, unused tags and labels, COC copies, etc. will be submitted to ER SMO.

The following is a list of necessary field documents:

- COC forms
- WAG 10 Groundwater Sample logbook which will include shipping data, field instrument calibration/standardization logbook, visitor's sign-in, and field team leader notes and comments
- Quality Assurance Project Plan (controlled copy)
- Field Sampling Plan and attachments (controlled copy)
- Health and Safety Plan (controlled copy)

#### 7.1 Field Documentation

**Labels**. A sample label will be used on each sample. Waterproof, gummed labels will be used. Labels may be affixed to sample containers before going to the field and completed on the actual sample date. The label will contain the sample collection time and date, preservation used, type of analysis, etc. Labels will remain in the custody of the FTL or his designee when not in use.

**Chain-of-Custody Forms.** The COC record is a multiple-copy form that serves as a written record of sample handling. When a sample changes custody, the person(s) relinquishing and receiving the sample will sign a COC record. Each change of possession will be documented. Thus, a written record tracking sample handling will be established. Additional COC information is found in MCP-244.

**Logbooks.** The Logbooks applicable to this project will be the WAG 10 Groundwater Sample logbook. MCP-231, "Logbooks for ER and D&D&D Projects," in accordance with ARDC format will be used to record information necessary to interpret the analytical data. All information pertaining to sampling activities will be entered in the logbooks. Entries will be dated and signed by the individual making the entry. All logbooks will be quality control (QC) checked for accuracy and completeness by the FTL or designee.

The field team will use WAG 10 Groundwater Sample logbook as a sample shipping logbook. Each sample will be entered in the logbook. This logbook will be used to record the sample ID number, collection date, shipping date, COC number, cooler number, destination, sample shipping classification, name of shipper, and signature of person performing quality control (QC) check.

Each piece of equipment, as necessary, will have information and a record in the WAG 10 Groundwater Sample logbook on the calibration data. Team members will record information pertaining to the calibration of equipment used during this project.

Daily accounting of information related to this sampling project, including problems encountered, deviations from the SAP, and justification for field decisions will be recorded by the FTL in the WAG 10 Groundwater Sample logbook. This logbook will also double as a visitor's logbook.

The nature of sampling activities is such that variations from the procedures are occasionally required to complete the task. These small deviations in the procedures are a one-time event for which a DAR is not necessary (MCP-231). These variations will be recorded in the WAG 10 Groundwater Sample logbook.

Copies of the logbook pages will be sent to the project at the completion of each round of sampling.

**Photographic Records.** To verify the well condition, the field team will collect a digital photograph of the well site and well head condition before and after sampling.

**Field Guidance Forms.** The field team may use field guidance forms to facilitate sample container documentation and organize field activities. Field guide forms contain information on the sample request number, sample ID number, sample location, aliquot number, analysis type, container size and type, and sample preservation.

**Waste Management Guidance.** For each well, the field team will be provided documentation regarding the approximate purge volume and the required waste management options for the purge volume.

# 7.2 Project Organization and Responsibility

Specific individuals (as needed) will be assigned the following project positions during performance of the monitoring activities:

- Safety engineer
- Field team leader
- Radiological Control Technician (RCT)

- Industrial hygienist
- Quality engineers
- Facility manager and/or representatives
- SMO point of contact
- Administrative record and document control (ARDC) coordinator
- Radiological engineer
- Occupational Medical Program representative
- Project manager
- Project engineer
- Task lead

With the exception of the SMO point of contact and the administrative record and document control coordinator, the Health and Safety Plan for the Environmental Restoration Sitewide Groundwater Monitoring (INEEL 2002) should be consulted for the overall organizational structure and specific personnel responsibilities. In addition to responsibility descriptions, the HASP ensures the implementation of occupational health and safety requirements.

# 8. WASTE MINIMIZATION

As part of the prejob briefing, an emphasis will be placed on waste reduction methods and personnel will be encouraged to continuously attempt to improve methods. No one will use, consume, spend, or expend equipment or materials thoughtlessly or carelessly. Practices to be instituted to support waste minimization include, but are not limited to the following. The project will:

- Restrict materials (especially hazardous material) to those needed for performance of work
- Substitute recyclable or burnable items for disposable items
- Reuse items when practical
- Segregate contaminated from uncontaminated waste
- Segregate reusable items such as PPE and tools.

# 9. HANDLING AND DISPOSITION OF INVESTIGATION DERIVED WASTE

All waste dispositioning will be coordinated with the appropriate Waste Generator Services (WGS) interface to ensure compliance with applicable waste storage, characterization, treatment, and disposal requirements.

The investigation-derived waste (IDW) produced during sampling will include spent and unused sample material, PPE, miscellaneous sampling supplies, decontamination water, purge water, and samples. The WGS will provide a determination for the disposition of all waste, including purge water, that is based on a waste determination and disposition form (WDDF). In addition to the WGS interface, Appendix G of the OU 10-08 RI/FS Work Plan (DOE-ID 2002) includes instructions for handling investigation-derived waste for this project.

Before sampling, the project will provide the field team with the WGS-generated WDDF for each well that describes the required disposal option for the purge water. Purge water from a majority of wells to be sampled under this FSP is anticipated to be eligible for release to the ground surface. In addition, to help ensure the purge volume is correct, the project will provide the samplers with the approximate volume of water that was purged from the well during a previous sampling round.

If, due to radionuclides, chemicals, or regulatory restrictions, the purged groundwater must be containerized for specific wells, then containerization will be done as long as a disposal option for the containerized purge water is available. If a purge water disposal option is not available, then WAG 10 will not sample the well. If the opportunity exists for those sites that have specific purge water disposal restrictions, the groundwater monitoring and sampling team will sample concurrently with other programs or WAGs to eliminate duplication and to provide for the most efficient and compliant management of purge water by those programs.

#### 10. QUALITY

The objective of this investigation is to provide groundwater sample analytical data of sufficient quality and quantity to fill the data gaps identified in DOE-ID 2001b. This FSP is used in conjunction with the QAPjP (DOE-ID 2001). These documents present the functional activities, organization, and quality assurance/quality control (QA/QC) protocols necessary to achieve the specified DQOs. The QAPjP and the FSP together constitute the sampling and analysis plan for OU 10-08. Project-specific quality requirements not addressed in the QAPjP or elsewhere in this document are discussed in this section.

# 10.1 Quality Control Sampling

As outlined in the QAPjP (DOE-ID 2001), QA objectives are specified so that the data produced are of a known and sufficient quality for determining whether a risk to human health or to the environment exists. Minimum precision, accuracy, and completeness measurements and minimum detection limits are quantitative objectives specified in the QAPjP. Representativeness and comparability are qualitative objectives. During the sampling discussed in this plan, field blanks, duplicates, equipment rinsates, and trip blanks will be collected and analyzed to evaluate the achievement of the precision and accuracy objectives specified in the QAPjP. Overall (field and laboratory) precision will be evaluated through the results of duplicate ground water samples, equipment rinsates, and field blanks. The duplicate samples, equipment rinsates, and field blanks will be analyzed for the same suite of analytes as the regular ground water samples. Trip blanks to be analyzed for volatile organic compounds (VOCs) will be included in each sample cooler shipped to the laboratory that contains VOC sample containers. The QA/QC samples to be collected and the planned analyses are shown in Appendix B.

#### 10.1.1 Performance Evaluation Samples

Environmental analyses are critical because decision-making based on inaccurate measurements or data of unknown quality can have significant economic and health consequences. To assess the accuracy and precision of the laboratory, performance evaluation (PE) samples will be added, if available, to sample delivery groups of ground water samples. The PE samples are spiked with known concentrations of radionuclides or chemicals in levels similar to those expected in the actual samples. Laboratory accuracy and precision will be evaluated based on their analytical results.

# 10.2 Quality Assurance Objectives

As outlined in the QAPjP (DOE-ID 2001), QA objectives are specified to ensure that data produced are of a known and sufficient quality. Minimum precision, accuracy, completeness requirements, and minimum detection limits are quantitative QA objectives specified in this plan or in the QAPjP. Representativeness and comparability are qualitative QA objectives.

#### 10.2.1 Precision and Accuracy

The precision of the data will be qualitatively assessed based on the results of duplicate samples. Laboratory precision and accuracy are part of the data validation criteria against which the results are evaluated. In addition, as discussed in Subsection 10.1.1, PE samples will help quantify laboratory accuracy and precision. In general, bias (accuracy) in the field is difficult to assess and in this investigation it will be qualitatively evaluated based on the results of field and equipment blanks.

### 10.2.2 Minimum Detection Limits

The minimum detection limits for this project correspond to MCLs. In all cases, the contract-required quantitation limits and contract-required detection limits will be at least one half the MCL.

#### 10.2.3 Critical Samples

Most of the proposed ground water samples are required to meet the project objectives; therefore, if ground water samples cannot be obtained, a determination will be made on a case-by-case basis as to whether an alternative well will be sampled.

#### 10.2.4 Representativeness

The representativeness of the collected data will be evaluated by confirming whether the sampling methods were adhered to and DQOs were met.

#### 10.2.5 Comparability

Data comparability will be assessed by evaluating the sampling procedures, sample handling, and laboratory analyses for each sample. If consistently applied for all samples, then the data are comparable.

#### 10.2.6 Completeness

Completeness is the measure of the quantity of the usable data that have been collected during an investigation. A goal of 100% is to be achieved for critical samples.

# 11. DATA VALIDATION, REDUCTION, AND REPORTING

Data validation for the groundwater analytical data will receive Level A validation. For each sample delivery group, a data limitation and validation report, which includes copies of COC forms, sample results, and validation flags, will be generated. All data limitation and validation reports will be transmitted to the EPA and Idaho Department of Environmental Quality (IDEQ) within 120 days from the last day of sample collection. All definitive data will be uploaded to the ground water sample analysis database.

#### 12. REFERENCES

- 40 CFR 261, 2001, "Identification and Listing of Hazardous Waste," *Code of Federal Regulations*, Office of the Federal Register, July 2001.
- 49 CFR Part 171, 2000, "General Information, Regulations, and Definitions," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 172, 2000, "Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements, *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 173, 2000, "Shippers--General Requirements for Shipments and Packagings," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 174, 2000, "Carriage by Rail," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 175, 2000, "Carriage by Aircraft," Code of Federal Regulations, Office of the Federal Register, October 2000.
- 49 CFR Part 176, 2000, "Carriage by Vessel," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 177, 2000, "Carriage by Public Highway," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 49 CFR Part 178, 2000, "Specifications for Packagings," *Code of Federal Regulations*, Office of the Federal Register, October 2000.
- 54 FR 29820, 1989, "National Priorities List for Uncontrolled Hazardous Waste Sites," *Federal Register*, United States Environmental Protection Agency, pp. 29820-29825, July 14, 1989.
- Bowman, A. L., W. F. Downs, K. S. Moor, and B. F. Russell, 1984, *INEL Environmental Characterization Report*, Vol. 2, EGG-NPR-6688, September 1984.
- DOE-ID, 1999, Work Plan for Waste Area Groups (WAGs) 6 and 10, Operable Unit 10-04 Comprehensive Remedial Investigation/Feasibility Study (RI/FS), DOE/ID-10554, Rev. 0, April 1999.
- DOE-ID, 2001, "Quality Assurance Project Plan for Waste Area Groups 1, 2, 3, 4, 5, 6, 7, 10, and Inactive Sites," DOE/ID-10587, Rev. 7, 2001.
- DOE-ID, 2002, "WAG 10, OU 10-08, Comprehensive Remedial Investigation/Feasibility Study Work Plan," DOE/ID-10902, Rev. 0, March 2002.
- EPA, 1988, Guidance for Conducting Remedial Investigations and Feasibility Studies Under CERCLA, Interim Final, EPA.540.G-89/004, 1988.
- INEEL, 2002, "Health and Safety Plan for the Environmental Restoration Long-Term Stewardship Sitewide Groundwater Monitoring, Rev 0, INEEL/EXT-01-01644, 2002.

- INEL, 1991, Federal Facility Agreement and Consent Order for the Idaho National Engineering Laboratory, December 1991.
- INEL, 1995, INEL Statement of Work for Organic Analyses Performed for the INEL Sample Management Office, ER-SOW-156, Rev. 1, April 1995
- MCP-135, "Creating, Modifying, and Canceling Procedures and Other DMCS-Controlled Documents," Rev. 10, General Administration and Information Management, October 2001.
- MCP-231, "Logbooks for ER and D&D&D Projects," Rev. 4, Environmental Protection and Compliance, July 2000.
- MCP-244, "Chain of Custody, Sample Handling, and Packaging for CERCLA Activities," Rev. 3, Environmental Restoration, September 1999.
- TPR-6541, "Decontaminating Sampling Equipment," June 2001.
- TPR-6566, "Measuring Groundwater Levels," November 2000.
- TPR-6570, "Sampling Groundwater," October 2000.

# Appendix A

**Figures Showing the Monitoring Well Locations** 




Figure A-1. INEEL baseline wells.




Figure A-2. INEEL boundary wells.




Figure A-3. INEEL guard wells.

# Appendix B Sampling and Analysis Plan Tables

Plan Table Number: OU10-08LONGTERM

SAP Number:	, Ta														Sample	Sampler: Gilbert, H. K.	Ή.Υ.						
Date: 04/10/2002	410/2002	Plan Table Revision: 0.0		Project OU ·	Project OU 10-08 GROUNDWATER SAMPLING	TER SAMPLING		Project Manager: WILKINSON, S. G.	KINSON, S. G.					¥s	SMO Contact ELDER, T. E.	£ ELDE	R. E.						
		Sample Description					Sample Location	cation						15	Enter Analysis Types (AT) and Quantity Requested	is Types	(AT) and	Quantify	y Reques	pest			
Sampling	Sample	Sample	8	Sampling	Pianned			Type of	Depth	AT1 AT2	AT3	AT4 AT	5 ATB	TA A	ATS ATS AT7 AT8 AT9 AT10 AT11 AT12 AT13 AT14 AT15 AT16 AT17AT18 AT19 AT20	4T10 AT	11 AT12	AT13 A	T14 AT1	5AT16/	AT17AT	18 AT1	9 AT20
Activity	Туре	Matrix	Туре	Method	Date	Area	Location	Localion		SX AV	ΥZ	aa Fi	8	& ₹	≅								
GWMB20	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-001	AQUIFER WELLS	288	-			-	-	-						_		
GWW921	REG	GROUND WATER	GRAB		04/15/2002	INELBOUNDARY	nscs-009	AQUIFER WELLS	209	_	Ţ	-	-		-							-	
GWM922	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	08CS-086	AQUIFER WELLS	648	-		-	Ξ	-	-	_			┢		$\vdash$	-	
GWWB23	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-101	AQUIFER WELLS	171	-		-	F	-	-				ļ		-	-	
GWM924	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-103	AQUIFER WELLS	583	-		-	-	-	-	_			-		┢	├	
GWW925	REG	GROUND WATER	SRAB		04/15/2002	INEELBOUNDARY	USGS-105	AQUIFER WELLS	0.29	-		-	-	-	-	_					ļ	-	
GWW926	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-108	AQUIFER WELLS	609	-		-	-	-	-	_		<u> </u>			<u> </u>	<del> </del>	
GWW927	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-109	AQUIFER WELLS	621	_		-	-	-	Ξ						_	-	
GWM928	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	USGS-110	AQUIFER WELLS	999			-	-	-	Ξ				-		<del> </del>	<u> </u>	
GWW929	REG	GROUND WATER	GRAB		04/15/2002	INEELBOUNDARY	HIGHWAY 2	AQUIFER WELLS	725	-		-	Ē	-	-				ļ			<u> </u>	
GWM930	REGIOC	GROUND WATER	ana		04/15/2002	GUARD WELLS	USGS-002	AQUIFER WELLS	629	_		2 2	7	2 2	2	_						_	
GWMB31	REG	GROUND WATER	GRAB		04/15/2002	GUARD WELLS	USGS-104	AQUIFER WELLS	999			-	-	-	-			_	_		-		
GWMB32	ဆ	WATER	PES		04/15/2002	GUARD WELLS	MP2	AQUIFER WELLS	08T	-				-							_	-	
GWMB33	8	WATER	PES		04/15/2002	GUARD WELLS	MP2	AQUIFER WELLS	TBD			-	1	-								_	
GWM834	8	WATER	PES		04/15/2002	GUARD WELLS	MP2	AQUIFER WELLS	TBD					1 1	1						-	_	
The samplin AT1: Nifroard	The sampling activity displayed on thi AT1: Nitroaromatics (8330) MSAMSD	The sampling activity displayed on this table represents the first six characters of the sample identification number. T: Nitroaromatics (6390) MSMASD	sthe first six	characters of th	ne sample identifica		ete sample identification num	The complete sample identification number (10 characters) will appear on field guidance forms and sample labels. AT11:	on field guidance forms an	d sample	labels.	Comments:	題										
AT2: VOCs (	VOCs (Appendix IX TAL)					AT12					1	Nitroaro	natics (	330)=1	Nitroaromatics (8330) = RDX, TNT								1
AT3: VOCs (	VOCs (Appendix IX TAL) - MS/MSD	.) - MS/MSD				AT13:	,					Total me	ta cont	winants	Total metai contaminants of potential concern (COPCs) are: arsenic, benyllium, cadmium,	ial conce	m (COP	Cs) are:	arsenic,	benyllium	n, cadmi	5	1
AT4: Tc-99						AT14:						chromitu	n, lead,	mercury	chromium, lead, mercury and zinc								
AT5: Total M	Total Metals (CLP TAL) - Filtered	- Filtered				AT15:																	1
AT6: Nitrate	Nitrate (as Nitrogen)					AT16.					ı												
AT7: Triffum						AT17:																	
AT8: Radioc	Radiochemistry - Suite 1					AT18:																ı	I
AT9: lodine-129	129					AT19:					ĺ												
AT10:						AT20:					1												
Analysis Suites: Radiochemistry	ss: try - Suite 1 inclux	Analysis Suites: Radiochemistry - Suite 1 includes: Gross Alpha, Gross Beta, Camma Spec, U-lso, Sr-90	eta, Gamma	Spec, U-Iso, Si	<u>8</u>			Confingencies:															
																		٠,			14		
																					İ	1	1

Plan Table Number: 0U10-08LONGTERM

SAP Number: Date: 04/10/2002

Project OU 10-08 GROUNDWATER SAMPLING Plan Table Revision: 0.0

Project Manager: WILKINSON, S. G.

SMO Contact ELDER, T. E. Sampler: Gilbert, H. K.

		Sample Description					Sample Location	xcation						Ē	эr Analysi	Enter Analysis Types (AT) and Quantity Requested	'AT) and	Quantity	Rednes	paj			
										AT1 AT2	AT3	AT4 ATE	ATS AT6	AT7 AT8	8 AT9	AT8 AT9 AT10 AT12 AT12 AT14 AT15 AT16 AT17 AT18 AT19 AT20	1 AT12	AT13A	T14AT1	5AT16	4T17AT	18 AT1	AT20
Sampling Activity	Sample Type	Sample Matrix	S  €	Sampling	Planned	Area	Location	Type of Location	Depth 5	SX AV	₹	<u>5</u>	8	& ₩	ā I				+		-	+	
GWM935	8	WATER	FBLK		04/15/2002	INEEL	8	FIELD BLANK	NA	-		-	-	-		$\vdash$			$\vdash$		$\vdash$	_	
GWM836	REG	GROUND WATER	GRAB		04/15/2002	GUARD WELLS	USGS-106	AQUIFER WELLS	584	_		-	Ξ	-	-	-			<u> </u>				
GWM937	REG	GROUND WATER	GRAB		04/15/2002	GUARD WELLS	USGS-107	AQUIFER WELLS	477	-		-	-	-	+								
GWM938	REG	GROUND WATER	GRAB		04/15/2002	GUARD WELLS	HIGHWAY 3	AQUIFER WELLS	538	-		-	=	-	-							_	
GWIMB39	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-004	AQUIFER WELLS	251	-		<del>-</del>	Ξ	-	Ξ	_					-		
GWM940	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-008	AQUIFER WELLS	766	_		-	Ξ	-	-	_					_		
GWM941	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-019	AQUIFER WELLS	276	_		-	÷	-	-	_			_			_	
GWM042	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-025	AQUIFER WELLS	272	-		-	Ξ	-	-	_			_		-	-	
GWM943	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-026	AQUIFER WELLS	212	-		-	Ξ	-	-	_					_		
GWM944	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	USGS-027	AQUIFER WELLS	228	-		-	_	-	-								
GWM945	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	DH-18	AQUIFER WELLS	268	-		-	Ξ	+	Ξ			_			-	_	
GWM946	REG	GROUND WATER	GRAB		04/15/2002	BASELINE WELLS	P&W-3	AQUIFER WELLS	304	-		-	-	-	-			-	_		$\vdash$	ļ	
GWM947	8	WATER	TBLK		04/15/2002	INEEL	ဘင	TRIP BLANK	NA	1								<del> </del>	L				
GWM948	8	WATER	TBLK		04/15/2002	INEEL	ဘင	TRIP BLANK	NA	1								-			_	ļ	
GWM649	8	WATER	TBLK		04/15/2002	INEEL	ઝ	TRIP BLANK	¥	-											_	ļ	
The sampling	activity displays	The sampling activity displayed on this table represents the first six characters of the sample identification number	s the first sio	characters of	the sample identific	١	ete sample identification nun	The complete sample identification number (10 cheracters) will appear on field guidance forms and sample labels	on field guidance forms and	sample	1	- dommonds	,	-		-		1	-	1	-	-	]
ATT: Nitroard	Nitroaromatics (8330) MS/MSD	SMSD				AT11:						liftoaron	nafics (8	330) = R	Nitroaromatics (8330) = RDX, TNT								
	VOCs (Appendix (X TAL)					AT12					 		1										
AT3: VCCs (A	VCCS (Appendix IX TAL) - MS/MSD	) - MS/MSD				AT13:						Total me	tal conta	minants	of potent	Total metal contaminants of potential concern (COPCs) are: arsenic, berylllum, cadmium,	FO0F	S) are:	arsenic,	berylltun	n, cadmit	ξ	1
AT4: Tc-99						AT14:					-, 	hromiu	n, lead, i	nercury	chromium, lead, mercury and zinc								1
AT5: Total Me	Total Metals (CLP TAL) - Filtered	- Filtered				AT15:														ŀ			1
AT6: Nitrate (	Nitrate (as Nitrogen)					AT16:																	
AT7: Tritium						AT17:					. , 					$ \  $							
AT8: Radioch	Radiochemistry - Suite 1					AT18:																	I
AT9: lodine-129	83					AT19:					· 												1
AT10:						AT20:					, . 												1
Analysis Suites:	24							Confingencies:															
Radiochemistr	y - Suite 1 inclue	Radiochemistry - Suite 1 includes: Gross Apha, Gross Beta, Gemma Spec, U-lso, Sr-90	Seta, Gamm	a Spec, U-lso,	Sr-90																		
																		11				$ \cdot $	
																							1
																							1

AT1 | AT2 | AT3 | AT4 | AT5 | AT6 | AT7 | AT8 | AT9 | AT10 | AT12 | AT12 | AT14 | AT15 | AT16 | AT17 | AT19 | AT20 | AT20 Total metal contaminants of potential concern (COPCs) are: arsenic, beryllium, cadmium, Enter Analysis Types (AT) and Quantity Requested SMO Contact ELDER, T.E. Sampler: Gilbert, H. K. Nitroaromatics (8330) = RDX, TNT chromium, lead, mercury and zinc 5X AV AZ EA LF Q6 R8 RH RI The complete sample identification number (10 characters) will appear on field guidance forms and sample labels. Depth (#) ¥ ¥ ¥ ¥ ≨ ≨ ¥ Project Manager: WILKINSON, S. G. Contingencies TRIP BLANK Type of Location Sample Location 8 ક 8 8 8 ႘ ဗ AT13: AT15: AT18: AT12: AT14: AT16: AT17: AT19: AT20. Project OU 10-08 GROUNDWATER SAMPLING NEEL NEE RE REF HE Area Ä REF The sampling activity displayed on this table represents the first six characters of the sample identification number. 04/15/2002 04/15/2002 04/15/2002 04/15/2002 04/15/2002 04/15/2002 04/15/2002 Planned Date Radiochemistry - Suite 1 includes: Gross Alpha, Gross Beta, Gamma Spec, U-Iso, Sr.90 Sampling Method TBLK TBLK TBLK TBLK **TBLK** TBLK Type Coll TBLK Plan Table Revision: 0.0 Sample Description OU10-08LONGTERM WATER WATER WATER WATER WATER WATER WATER Sample Matrix VOCs (Appendix IX TAL) - MS/MSD Total Metals (CLP TAL) - Filtered Nitroaromatics (8330) MS/MSD VOCs (Appendix IX TAL) Radiochemistry - Suite 1 Nifrate (as Nifrogen) Sample Type မွ 8 8 ဗ 8 8 8 Plan Table Number. Date: 04/10/2002 AT9: lodine-129 SAP Number: Analysis Suites: 75 98 GWM950 GWM951 GWN952 GWM953 GWM954 GWM955 Sampling Activity GWM956 AT10: \_\_\_\_ AT3: AT8: AT2: AT5: AT7: AT4: AT6: