

**Appendix BB**  
**Detailed Cost Estimate**



# Appendix BB

## Detailed Cost Estimate

To prepare the detailed cost estimate for the INEEL CERCLA Disposal Facility project, the following information is the basis for the cost estimate.

**SCOPE OF WORK:** Brief description of the proposed project.

The scope of this project is to complete the remaining 2002 work on the ICDF.

**BASIS OF THE ESTIMATE:** Drawings, Design Report, Engineers' Notes and/or other documentation upon which the estimate is originated.

- A. CH2M HILL 90% design drawings and specifications
- B. TEREX Earth Moving Handbook
- C. Caterpillar Handbook
- D. Means Cost Data
- E. Richardson Estimating Manual
- F. Previous approved for construction (AFC) estimate

**ASSUMPTIONS:** Conditions statements accepted or supposed true without proof of demonstration. An assumption has a direct impact on total estimated cost.

- A. Work to be performed in 2002.
- B. Work will be performed by a contractor familiar with construction at the Idaho National Engineering and Environmental Laboratory (INEEL).
- C. No hazardous or contaminated material will be encountered.
- D. All radiological technicians and environmental, safety, and quality support will be available to support the work.
- E. No costs have been included to decontaminate, clean, or replace any equipment.
- F. INEEL Site-specific training required by the contract is not included.
- G. Costs for Conduct of Operations/Conduct of Maintenance are included.
- H. Entire fence will not have to be grounded, only the portion of the fence near the power lines.
- I. Roads will be paved with 4 in. of AC over 6 in. of base.

- J. No costs have been included for any controls to be run back to the Staging, Storage, Sizing, and Treatment Facility.
- K. Evaporation pond structural fill is 1 ft of material from Rye Grass Flats to protect the secondary membrane from the rocks.
- L. All pipe inside the crest buildings is carbon steel.
- M. All fire protection pipe is PVC.
- N. All other pipe is HDPE.

**CONTINGENCY GUIDELINE IMPLEMENTATION:** *The percentage used for contingency as determined by the contingency allowance guidelines can be altered to reflect the type of construction and conditions that may impact the total estimated cost.*

A 6% contingency has been included in the estimate<sup>1</sup>. This is within the acceptable range for an estimate at 90% design where detailed design has been completed and used for the cost estimate. The activities with the largest contingency are as follows:

- Equipment mobilization
- Utility excavation and fill
- Concrete
- Finish painting
- Landfill pipe and pumps
- Evaporation pond crest building piping
- All electrical.

**OTHER COMMENTS/CONCERNS SPECIFIC TO THE ESTIMATE:**

- A. Costs on the detailed cost sheets are direct costs and do not include overhead, profit, or escalation for the construction subcontractor.
- B. Each major activities cost has been escalated to the midpoint of that activity on the summary sheets.
- C. Ten percent has been added to all work activities to spread direct supervision and quality assurance/quality control costs back into the work.

---

1. Contingency decreases for each stage of a project at which the cleanup estimate is prepared. For the detailed design phase, contingency is typically +/- 10%.

The Table BB-1 summarizes the construction cost estimate for the remainder of construction for ICDF. The estimate construction cost is \$6,897,942.

One further cost comparison is provided in this section. A comparison is made between the estimated cost in the Feasibility Study (DOE-ID 1998) to the same cost in the Remedial Design/Construction Work Plan (RD/CWP). The estimated cost for the ICDF project has been reduced by approximately \$32 million as detailed in Table BB-2. The cost of on-Site disposal at the ICDF Complex has been significantly reduced from the estimate in the Feasibility Study (FS) Supplement Report (DOE-ID 1998), on which the Operable Unit 3-13 Record of Decision was based. The current estimate for on-Site disposal at the ICDF Complex is \$79.6M, which includes design, construction, operation, closure, and long-term monitoring. The most significant scope change is that minimal treatment facilities will be constructed and operated at the ICDF Complex instead of a complex treatment system capable of treating 20,000 yd<sup>3</sup>/yr. The complex treatment system was planned to treat a wide variety of wastes using several treatment processes. The minimal treatment facility will use one treatment process.

The estimated costs are summarized for on-Site and off-Site disposal (Hain 2001) as follows. The off-Site disposal cost is estimated to cost \$465M and, based upon disposal of 510,000 yd<sup>3</sup>, the cost of disposal is \$911/yd<sup>3</sup>. The on-Site disposal cost is \$79.6M and, based upon the same volume, the cost of disposal is \$156/yd<sup>3</sup>. On-Site disposal costs are \$385.4M less than off-Site disposal while the estimated cost per cubic yard is \$755/yd<sup>3</sup> less for on-Site disposal. Effective July 1, 2001, Utah began issuing permits and assessing fees to generators for accessing Utah radioactive waste disposal facilities (Rule R313-26). The annual fee for generators who generate more than 1,000 ft<sup>3</sup> is \$1,300. If INEEL wastes were shipped to Utah over a 15-year time frame, the off-Site disposal cost would increase \$19,500 or \$0.04/yd<sup>3</sup>.

#### **REFERENCES:**

- DOE-ID, 1998. *Comprehensive RI/FS for the Idaho Chemical Processing Plant OU 3-13 at the INEEL-Part B, FS Supplement Report*, Volume 2, Appendix A, DOE/ID-10619, Revision 2, October 1998.
- Hain, 2001, Kathleen Hain, Manager Environmental Restoration Program, Department of Energy, Idaho Operations Office, to, Wayne Pierre, Environmental Cleanup Office, U.S. Environmental Protection Agency, Region X and Dean Nygard, Idaho Department of Environmental Quality, Date, October 3, 2001, Subject, "On-Site Versus Off-Site Soil and Debris Disposal Cost Comparison," Enclosure: *On-site Versus Off-Site Soil and Debris Disposal Comparison for the ICDF Complex*, October 2001.
- Rule R313-26, 2001, "Generator Site Access Permit Requirements for Accessing Utah Radioactive Waste Disposal Facilities," Utah Administrative Code, Environmental Quality, September 2001.

Table BB-1. ICDF Phase II construction cost summary.

Description	Direct Cost (\$)	Sales Tax (\$)	Sub Overhead (\$)	Escalation (\$)	Contingency (\$)	Total Cost (\$)
Install sediment & erosion control	9,129	78	4,878	338	1,154	15,577
Clear, grub & strip borrow area	21,744	0	11,587	800	2,730	36,861
Place ICDF structural fill	85,777	1,838	46,687	3,223	11,002	148,527
Place ICDF HDPE geomembrane	155,351	5,466	110,742	6,517	22,246	300,322
Place ICDF composite drainage net	104,335	2,915	73,855	4,347	14,836	200,288
Place evaporation pond clay liner	125,057	2,767	88,023	5,180	17,682	238,709
Revegetation	10,522	240	5,735	396	1,351	18,244
Site cleanup	12,754	0	6,796	469	1,602	21,621
Install monitoring & control systems	6,898	250	3,809	263	1,306	12,526
Subcontractor mobilization	38,192	0	11,294	1,188	10,135	60,809
Place ICDF clay liner	330,788	7,288	232,807	13,701	46,767	631,351
Place ICDF secondary HDPE	155,351	5,466	110,742	6,517	22,246	300,322
Place ICDF composite drainage net	104,335	2,915	73,855	4,347	14,836	200,288
Place ICDF primary clay liner	391,669	640	209,052	14,433	49,263	665,057
Place ICDF leachate drainage gravel	115,392	4,800	64,047	4,422	15,093	203,754
Place leachate collection piping & pumps	46,483	1,042	28,492	1,824	6,227	84,068
Place ICDF landfill operations layer	251,020	2,915	152,020	9,743	33,256	448,954
Construct ICDF crest pad building	89,060	3,111	53,143	3,488	14,670	163,472
Place evaporation pond secondary liner	59,003	2,076	42,062	2,475	8,449	114,065
Place evaporation pond composite drainage net	79,253	2,214	56,101	3,302	11,270	152,140
Construct evaporation pond crest building	44,943	1,279	25,595	1,724	8,649	82,190
Place evaporation pond primary HDPE	118,005	4,152	84,120	4,951	16,898	228,126

Table BB-1. (continued).

Description	Direct Cost (\$)	Sales Tax (\$)	Sub Overhead (\$)	Escalation (\$)	Contingency (\$)	Total Cost (\$)
Construct lechate transfer facility	34,841	743	19,292	1,317	6,602	62,795
Install electrical power systems	82,951	739	45,885	3,110	14,520	147,205
Install raw water system	175,166	1,539	99,381	6,626	22,617	305,329
Place surface course for roads	132,794	1,100	71,349	4,926	16,814	226,983
Install perimeter fence	129,896	3,828	71,258	4,920	16,902	226,804
Install groundwater monitoring wells	1,410,584	0	0	0	190,972	1,601,555
<b>Total ICDF Phase II</b>						<b>\$6,897,942</b>

Table BB-2. Cost comparison between feasibility study and RD/CWP.

Cost Element	Feasibility Study Estimated Cost (DOE-ID 1998)	RD/CWP Estimated Cost (Hain 2001)
Capital	\$91,955,000	\$31,627,000
Design	\$6,898,000	\$8,451,000
Construction	\$85,057,000	\$23,176,000
Operations total	\$11,514,000	\$21,486,000
Closure total	NA <sup>a</sup>	\$9,969,000
Post-closure total	\$8,213,000	\$7,995,000
Other cost total <sup>b</sup>	NA <sup>a</sup>	\$8,550,000
Total	\$111,682,000	\$79,627,000
<b>Difference</b>	<b>\$32,055,000</b>	

a. N/A = Not included in Feasibility Study cost estimate.

b. Other costs include program management necessary to implement a project at the INEEL for a duration of 100 years.

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>SIC</u>	<u>Other</u>	<u>TOTAL*</u>
-	CB6706									
--	WBS 9102.1.01									
	DIRT	U.C. per hr 120.00	2	CN-LABR \$31.58	63.16 \$7,579	0 \$0	0 \$0	0 \$0	0 \$0	63.16 \$7,579
	Silt Fence	U.C. per lf 3,000.00	0		0 \$0	0 \$0	0.5 \$1,500	0 \$0	0 \$0	0.5 \$1,500
	Straw bales	U.C. per ea 100.00	0		0 \$0	0 \$0	0.5 \$50	0 \$0	0 \$0	0.5 \$50
<hr/>										
	Subtotal WBS 9102.1.01				\$7,579	\$0	\$1,550	\$0	\$0	\$9,129
	Sales Tax				\$0	\$0	\$78	\$0	\$0	\$78
	INEEL Org Labor/Subcontractor Overheads				\$4,039	\$0	\$839	\$0	\$0	\$4,878
	Escalation				\$279	\$0	\$59	\$0	\$0	\$338
	Contingency				\$952	\$0	\$202	\$0	\$0	\$1,154
	<b>-- Total WBS 9102.1.01</b>		<b>240</b>		<b>\$12,849</b>	<b>\$0</b>	<b>\$2,728</b>	<b>\$0</b>	<b>\$0</b>	<b>\$15,577</b>
<hr/>										
	Subtotal CB6706				\$7,579	\$0	\$1,550	\$0	\$0	\$9,129
	Sales Tax				\$0	\$0	\$78	\$0	\$0	\$78
	INEEL Org Labor/Subcontractor Overheads				\$4,039	\$0	\$839	\$0	\$0	\$4,878
	Escalation				\$279	\$0	\$59	\$0	\$0	\$338
	Contingency				\$952	\$0	\$202	\$0	\$0	\$1,154
	<b>- Total CB6706</b>		<b>240</b>		<b>\$12,849</b>	<b>\$0</b>	<b>\$2,728</b>	<b>\$0</b>	<b>\$0</b>	<b>\$15,577</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
-	CB6707										
--	WBS 9102.1.02										
	Clear & Grub	U. C. per ac 40.00	0		199.2 \$7,968	344.4 \$13,776		0 \$0	0 \$0	0 \$0	543.6 \$21,744
	Subtotal WBS 9102.1.02				\$7,968	\$13,776		\$0	\$0	\$0	\$21,744
	Sales Tax				\$0	\$0		\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$4,246	\$7,341		\$0	\$0	\$0	\$11,587
	Escalation				\$293	\$507		\$0	\$0	\$0	\$800
	Contingency				\$1,001	\$1,730		\$0	\$0	\$0	\$2,730
	<b>-- Total WBS 9102.1.02</b>				<b>\$13,508</b>	<b>\$23,354</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$36,861</b>
	Subtotal CB6707				\$7,968	\$13,776		\$0	\$0	\$0	\$21,744
	Sales Tax				\$0	\$0		\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$4,246	\$7,341		\$0	\$0	\$0	\$11,587
	Escalation				\$293	\$507		\$0	\$0	\$0	\$800
	Contingency				\$1,001	\$1,730		\$0	\$0	\$0	\$2,730
	<b>- Total CB6707</b>				<b>\$13,508</b>	<b>\$23,354</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$36,861</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const	Eqp	Matl	S/C	Other	TOTAL*
. CB6709											
-- WBS 9102.2.10											
Grader	DIRT	U.C. per hr 80.00	1 80	00E0912	0 \$0	0 \$5,270	65.87 \$5,270	0 \$0	0 \$0	0 \$0	65.87 \$5,270
00E0612	DIRT	U.C. per hr 80.00	1 80	00E0612	0 \$0	0 \$8,108	101.35 \$8,108	0 \$0	0 \$0	0 \$0	101.35 \$8,108
00E2052	DIRT	U.C. per hr 80.00	1 80	00E2052	0 \$0	0 \$10,142	126.77 \$10,142	0 \$0	0 \$0	0 \$0	126.77 \$10,142
10000 gal Water Wagon											
Operator & Grade Checker	DIRT	U.C. per hr 80.00	4 320	CN-EQMD \$34.75	139 \$11,120	0 \$0	0 \$0	0 \$0	0 \$0	0 \$0	139 \$11,120
Labor	DIRT	U.C. per hr 80.00	2 160	CN-LABR \$31.58	63.16 \$5,053	0 \$0	0 \$0	0 \$0	0 \$0	0 \$0	63.16 \$5,053
Subtotal	WBS 9102.2.10				\$16,173	\$23,519		\$0	\$0	\$0	\$39,692
Sales Tax					\$0	\$0		\$0	\$0	\$0	\$0
INEEL Org Labor/Subcontractor Overheads					\$8,618	\$12,533		\$0	\$0	\$0	\$21,151
Escalation					\$595	\$865		\$0	\$0	\$0	\$1,460
Contingency					\$2,031	\$2,953		\$0	\$0	\$0	\$4,984
-- Total	WBS 9102.2.10		480		\$27,417	\$39,871		\$0	\$0	\$0	\$67,287
-- WBS 9102.2.11											
Load and Haul Select Material	DIRT	U.C. per cy 2,450.00	0		0.66 \$1,617	0.94 \$2,303		15 \$36,750	0 \$0	0 \$0	16.6 \$40,670

**INEEL**

\*Note: Total Excludes PF, G&A, and OFC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	Spread and Compact	U.C. per cy 2,450.00	0		1.01 \$2,475	1.2 \$2,940	0 \$0	0 \$0	0 \$0	2.21 \$5,415
	DIRT									
	Subtotal WBS 9102.2.11				\$4,092	\$5,243	\$36,750	\$0	\$0	\$46,085
	Sales Tax				\$0	\$0	\$1,838	\$0	\$0	\$1,838
	INEEL Org Labor/Subcontractor Overheads				\$2,180	\$2,794	\$20,562	\$0	\$0	\$25,537
	Escalation				\$151	\$193	\$1,420	\$0	\$0	\$1,763
	Contingency				\$514	\$658	\$4,846	\$0	\$0	\$6,018
	<b>-- Total WBS 9102.2.11</b>				<b>\$6,936</b>	<b>\$8,888</b>	<b>\$65,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$81,239</b>
	Subtotal CB6709				\$20,264	\$28,762	\$36,750	\$0	\$0	\$85,777
	Sales Tax				\$0	\$0	\$1,838	\$0	\$0	\$1,838
	INEEL Org Labor/Subcontractor Overheads				\$10,798	\$15,327	\$20,562	\$0	\$0	\$46,687
	Escalation				\$746	\$1,058	\$1,420	\$0	\$0	\$3,223
	Contingency				\$2,545	\$3,612	\$4,846	\$0	\$0	\$11,002
	<b>- Total CB6709</b>		480		<b>\$34,353</b>	<b>\$48,759</b>	<b>\$65,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$148,527</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const	Eqp	Matl	S/C	Other	TOTAL*
. CB6713											
-- WBS 9102.1.35											
60 mill HDPE		U.C. per sf 364,400.00	0.004 1,458	CN-LABR \$31.58	0.126 \$46,031		0 \$0	0.3 \$109,320	0 \$0	0 \$0	0.426 \$155,351
Subtotal	WBS 9102.1.35				\$46,031		\$0	\$109,320	\$0	\$0	\$155,351
Sales Tax					\$0		\$0	\$5,466	\$0	\$0	\$5,466
INEEL Org Labor/Subcontractor Overheads					\$31,698		\$0	\$79,044	\$0	\$0	\$110,742
Escalation					\$1,865		\$0	\$4,652	\$0	\$0	\$6,517
Contingency					\$6,368		\$0	\$15,879	\$0	\$0	\$22,246
<b>-- Total</b>	<b>WBS 9102.1.35</b>		<b>1,458</b>		<b>\$85,962</b>		<b>\$0</b>	<b>\$214,361</b>	<b>\$0</b>	<b>\$0</b>	<b>\$300,323</b>
Subtotal	CB6713				\$46,031		\$0	\$109,320	\$0	\$0	\$155,351
Sales Tax					\$0		\$0	\$5,466	\$0	\$0	\$5,466
INEEL Org Labor/Subcontractor Overheads					\$31,698		\$0	\$79,044	\$0	\$0	\$110,742
Escalation					\$1,865		\$0	\$4,652	\$0	\$0	\$6,517
Contingency					\$6,368		\$0	\$15,879	\$0	\$0	\$22,246
<b>- Total</b>	<b>CB6713</b>		<b>1,458</b>		<b>\$85,962</b>		<b>\$0</b>	<b>\$214,361</b>	<b>\$0</b>	<b>\$0</b>	<b>\$300,323</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
. CB6715										
-- WBS 9102.1.40										
16 oz Geotex		U. C. per sf 364,400.00	0.004 1,458	CN-LABR \$31.58	0.126 \$46,031	0 \$0	0.16 \$58,304	0 \$0	0 \$0	0.286 \$104,335
Subtotal	WBS 9102.1.40				\$46,031	\$0	\$58,304	\$0	\$0	\$104,335
Sales Tax					\$0	\$0	\$2,915	\$0	\$0	\$2,915
INEEL Org Labor/Subcontractor Overheads					\$31,698	\$0	\$42,157	\$0	\$0	\$73,855
Escalation					\$1,865	\$0	\$2,481	\$0	\$0	\$4,347
Contingency					\$6,368	\$0	\$8,469	\$0	\$0	\$14,836
<b>-- Total WBS 9102.1.40</b>			<b>1,458</b>		<b>\$85,962</b>	<b>\$0</b>	<b>\$114,326</b>	<b>\$0</b>	<b>\$0</b>	<b>\$200,288</b>
Subtotal	CB6715				\$46,031	\$0	\$58,304	\$0	\$0	\$104,335
Sales Tax					\$0	\$0	\$2,915	\$0	\$0	\$2,915
INEEL Org Labor/Subcontractor Overheads					\$31,698	\$0	\$42,157	\$0	\$0	\$73,855
Escalation					\$1,865	\$0	\$2,481	\$0	\$0	\$4,347
Contingency					\$6,368	\$0	\$8,469	\$0	\$0	\$14,836
<b>- Total CB6715</b>			<b>1,458</b>		<b>\$85,962</b>	<b>\$0</b>	<b>\$114,326</b>	<b>\$0</b>	<b>\$0</b>	<b>\$200,288</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
. CB6725											
-- WBS 9102.2.25											
	LINE										
	Geosynthetic Clay Liner	U.C. per sf 138,400.00	0.015 2,076	CN-LABR \$31.58	0.474 \$65,560	0 \$0	0 \$0	0.4 \$55,360	0 \$0	0 \$0	0.874 \$120,920
	LINE										
	00E1310 Grove RT522 20 tn Crane	U.C. per hr 40.00	1 40	00E1310 \$34.75	34.75 \$1,390	68.68 \$2,747	0 \$0	0 \$0	0 \$0	0 \$0	103.43 \$4,137
	Subtotal WBS 9102.2.25				\$66,950	\$2,747		\$55,360	\$0	\$0	\$125,057
	Sales Tax				\$0	\$0		\$2,768	\$0	\$0	\$2,768
	INEEL Org Labor/Subcontractor Overheads				\$46,103	\$1,892		\$40,028	\$0	\$0	\$88,023
	Escalation				\$2,713	\$111		\$2,356	\$0	\$0	\$5,180
	Contingency				\$9,261	\$380		\$8,041	\$0	\$0	\$17,682
	<b>-- Total WBS 9102.2.25</b>		<b>2,076</b>		<b>\$125,028</b>	<b>\$5,130</b>		<b>\$108,553</b>	<b>\$0</b>	<b>\$0</b>	<b>\$238,711</b>
	Subtotal CB6725				\$66,950	\$2,747		\$55,360	\$0	\$0	\$125,057
	Sales Tax				\$0	\$0		\$2,768	\$0	\$0	\$2,768
	INEEL Org Labor/Subcontractor Overheads				\$46,103	\$1,892		\$40,028	\$0	\$0	\$88,023
	Escalation				\$2,713	\$111		\$2,356	\$0	\$0	\$5,180
	Contingency				\$9,261	\$380		\$8,041	\$0	\$0	\$17,682
	<b>- Total CB6725</b>		<b>2,076</b>		<b>\$125,028</b>	<b>\$5,130</b>		<b>\$108,553</b>	<b>\$0</b>	<b>\$0</b>	<b>\$238,711</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>SIC</u>	<u>Other</u>	<u>TOTAL*</u>
. CB6750										
-- WBS 9101.2.01										
Seed Area	DIRT	U.C. per hr 40.00	1 40	CN-EQMD \$34.75	34.75 \$1,390	36.78 \$1,471	100 \$4,000	0 \$0	0 \$0	171.53 \$6,861
Spread Straw	DIRT	U.C. per hr 40.00	1 40	CN-EQMD \$34.75	34.75 \$1,390	36.78 \$1,471	20 \$800	0 \$0	0 \$0	91.53 \$3,661
Subtotal	WBS 9101.2.01				\$2,780	\$2,942	\$4,800	\$0	\$0	\$10,522
Sales Tax					\$0	\$0	\$240	\$0	\$0	\$240
INEEL Org Labor/Subcontractor Overheads					\$1,481	\$1,568	\$2,686	\$0	\$0	\$5,735
Escalation					\$102	\$108	\$185	\$0	\$0	\$396
Contingency					\$349	\$369	\$633	\$0	\$0	\$1,351
<b>-- Total WBS 9101.2.01</b>			<b>80</b>		<b>\$4,713</b>	<b>\$4,988</b>	<b>\$8,544</b>	<b>\$0</b>	<b>\$0</b>	<b>\$18,245</b>
Subtotal	CB6750				\$2,780	\$2,942	\$4,800	\$0	\$0	\$10,522
Sales Tax					\$0	\$0	\$240	\$0	\$0	\$240
INEEL Org Labor/Subcontractor Overheads					\$1,481	\$1,568	\$2,686	\$0	\$0	\$5,735
Escalation					\$102	\$108	\$185	\$0	\$0	\$396
Contingency					\$349	\$369	\$633	\$0	\$0	\$1,351
<b>- Total CB6750</b>			<b>80</b>		<b>\$4,713</b>	<b>\$4,988</b>	<b>\$8,544</b>	<b>\$0</b>	<b>\$0</b>	<b>\$18,245</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
. CB6751											
-- WBS 9101.2.02											
	DI RT	U.C. per hr	1	CN-EQMD	34.75		31.45	0	0	0	66.2
	Dump Truck w/ Teamster	40.00	40	\$34.75	\$1,390		\$1,258	\$0	\$0	\$0	\$2,648
	DI RT	U.C. per hr	4	CN-LABR	126.32		0	0	0	0	126.32
	Laborer	80.00	320	\$31.58	\$10,106		\$0	\$0	\$0	\$0	\$10,106
	Subtotal WBS 9101.2.02				\$11,496		\$1,258	\$0	\$0	\$0	\$12,754
	Sales Tax				\$0		\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$6,126		\$670	\$0	\$0	\$0	\$6,796
	Escalation				\$423		\$46	\$0	\$0	\$0	\$469
	Contingency				\$1,444		\$158	\$0	\$0	\$0	\$1,602
	<b>-- Total WBS 9101.2.02</b>		<b>360</b>		<b>\$19,488</b>		<b>\$2,133</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$21,620</b>
	Subtotal CB6751				\$11,496		\$1,258	\$0	\$0	\$0	\$12,754
	Sales Tax				\$0		\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$6,126		\$670	\$0	\$0	\$0	\$6,796
	Escalation				\$423		\$46	\$0	\$0	\$0	\$469
	Contingency				\$1,444		\$158	\$0	\$0	\$0	\$1,602
	<b>- Total CB6751</b>		<b>360</b>		<b>\$19,488</b>		<b>\$2,133</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$21,620</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
-	CB6755									
--	WBS 9102.3.06									
	Foundation Excavation	U.C. per hr 10.00	1 10	CN-EQMD \$34.75	34.75 \$348	28.68 \$287	0 \$0	0 \$0	0 \$0	63.43 \$634
	Subtotal WBS 9102.3.06				\$348	\$287	\$0	\$0	\$0	\$634
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$185	\$153	\$0	\$0	\$0	\$338
	Escalation				\$13	\$11	\$0	\$0	\$0	\$23
	Contingency				\$44	\$36	\$0	\$0	\$0	\$80
--	<b>Total WBS 9102.3.06</b>		<b>10</b>		<b>\$589</b>	<b>\$486</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,075</b>
--	WBS 9103.3.03									
	Precast Manhole	U.C. per ea 1.00	40 40	CN-LABR \$31.58	1263.2 \$1,263	0 \$0	5000 \$5,000	0 \$0	0 \$0	6263.2 \$6,263
	Subtotal WBS 9103.3.03				\$1,263	\$0	\$5,000	\$0	\$0	\$6,263
	Sales Tax				\$0	\$0	\$250	\$0	\$0	\$250
	INEEL Org Labor/Subcontractor Overheads				\$673	\$0	\$2,798	\$0	\$0	\$3,471
	Escalation				\$46	\$0	\$193	\$0	\$0	\$240
	Contingency				\$238	\$0	\$989	\$0	\$0	\$1,227
--	<b>Total WBS 9103.3.03</b>		<b>40</b>		<b>\$2,221</b>	<b>\$0</b>	<b>\$9,230</b>	<b>\$0</b>	<b>\$0</b>	<b>\$11,450</b>
-	CB6755									
	Subtotal CB6755				\$1,611	\$287	\$5,000	\$0	\$0	\$6,898
	Sales Tax				\$0	\$0	\$250	\$0	\$0	\$250
	INEEL Org Labor/Subcontractor Overheads				\$858	\$153	\$2,798	\$0	\$0	\$3,809
	Escalation				\$59	\$11	\$193	\$0	\$0	\$263
	Contingency				\$282	\$36	\$989	\$0	\$0	\$1,306
-	<b>Total CB6755</b>		<b>50</b>		<b>\$2,810</b>	<b>\$486</b>	<b>\$9,230</b>	<b>\$0</b>	<b>\$0</b>	<b>\$12,526</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
. CBA6704										
-- WBS 9102.2.01										
00E0610	DIRT	U.C. per hr	1	00E0610	0	75.65	0	0	0	75.65
Cat 815 Sheepsfoot		10.00	10		\$0	\$757	\$0	\$0	\$0	\$757
00E0620	DIRT	U.C. per hr	1	00E0620	0	11.82	0	0	0	11.82
Bowmag BW90 Compactor		10.00	10		\$0	\$118	\$0	\$0	\$0	\$118
00E0912	DIRT	U.C. per hr	1	00E0912	0	65.87	0	0	0	65.87
Cat 14 Grader		10.00	10		\$0	\$659	\$0	\$0	\$0	\$659
00E0940	DIRT	U.C. per hr	1	00E0940	0	43.83	0	0	0	43.83
Cat 950.4 cy Loader		10.00	10		\$0	\$438	\$0	\$0	\$0	\$438
00E0962	DIRT	U.C. per hr	1	00E0962	0	86.72	0	0	0	86.72
Cat D7 Dozer		10.00	10		\$0	\$867	\$0	\$0	\$0	\$867
CN-MGR	GEN	U.C. per ls	0	CN-MGR	0	0	0	0	10000	10000
Manager		1.00	0		\$0	\$0	\$0	\$0	\$10,000	\$10,000
CN-ENG	GEN	U.C. per ls	0	CN-ENG	0	0	0	0	10000	10000
Engineer		1.00	0		\$0	\$0	\$0	\$0	\$10,000	\$10,000
00E1010	DIRT	U.C. per hr	1	00E1010	0	53.64	0	0	0	53.64
Cat 320 1.25 cy Hoe		10.00	10		\$0	\$536	\$0	\$0	\$0	\$536
00E1310	DIRT	U.C. per hr	1	00E1310	0	68.68	0	0	0	68.68
Grove RT522 20 tn Crane		10.00	10		\$0	\$687	\$0	\$0	\$0	\$687
00E1910	DIRT	U.C. per hr	6	00E1910	0	295.02	0	0	0	295.02
30 tn Bottom Dump Trk.		10.00	60		\$0	\$2,950	\$0	\$0	\$0	\$2,950
00E2010	DIRT	U.C. per hr	4	00E2010	0	125.8	0	0	0	125.8
12 cy End Dump		10.00	40		\$0	\$1,258	\$0	\$0	\$0	\$1,258
00E2050	DIRT	U.C. per hr	1	00E2050	0	31.38	0	0	0	31.38
4000 gal Water Truck		10.00	10		\$0	\$314	\$0	\$0	\$0	\$314
00E2052	DIRT	U.C. per hr	1	00E2052	0	126.77	0	0	0	126.77
10000 gal Water Wagon		10.00	10		\$0	\$1,268	\$0	\$0	\$0	\$1,268
CN-EQMD	DIRT	U.C. per hr	5	CN-EQMD	173.75	0	0	0	0	173.75
Equipment Operators, Medium Equipment		40.00	200	\$34.75	\$6,950	\$0	\$0	\$0	\$0	\$6,950

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	CN-EQMM	U.C. per hr								
	Equipment Operators, Master Mechanics	40.00	40	\$34.75	\$1,390	\$0	\$0	\$0	\$0	\$1,390
	DIRT									
	Subtotal WBS 9102.2.01				\$8,340	\$9,852	\$0	\$0	\$20,000	\$38,192
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$4,444	\$5,250	\$0	\$0	\$1,600	\$11,294
	Escalation				\$307	\$362	\$0	\$0	\$518	\$1,188
	Contingency				\$2,618	\$3,093	\$0	\$0	\$4,424	\$10,135
	<b>-- Total WBS 9102.2.01</b>		<b>240</b>		<b>\$15,709</b>	<b>\$18,557</b>	<b>\$0</b>	<b>\$0</b>	<b>\$26,542</b>	<b>\$60,808</b>
	Subtotal CBA6704				\$8,340	\$9,852	\$0	\$0	\$20,000	\$38,192
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$4,444	\$5,250	\$0	\$0	\$1,600	\$11,294
	Escalation				\$307	\$362	\$0	\$0	\$518	\$1,188
	Contingency				\$2,618	\$3,093	\$0	\$0	\$4,424	\$10,135
	<b>- Total CBA6704</b>		<b>240</b>		<b>\$15,709</b>	<b>\$18,557</b>	<b>\$0</b>	<b>\$0</b>	<b>\$26,542</b>	<b>\$60,808</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
..	CBA6708										
..	WBS 9102.1.30										
	LINE										
	Geosynthetic Clay Liner	U.C. per sf 364,400.00	0.015 5,466	CN-LABR \$31.58	0.474 \$172,616	0 \$0	\$0	0.4 \$145,760	0 \$0	0 \$0	0.874 \$318,376
	LINE										
	00E1310	U.C. per hr 120.00	1 120	00E1310 \$34.75	34.75 \$4,170	68.68 \$8,242	\$0	0 \$0	0 \$0	0 \$0	103.43 \$12,412
	Grove RT522 20 In Crane										
	Subtotal				\$176,786	\$8,242	\$0	\$145,760	\$0	\$0	\$330,788
	Sales Tax				\$0	\$0	\$0	\$7,288	\$0	\$0	\$7,288
	INEEL Org Labor/Subcontractor Overheads				\$121,739	\$5,675	\$0	\$105,392	\$0	\$0	\$232,807
	Escalation				\$7,165	\$334	\$0	\$6,203	\$0	\$0	\$13,701
	Contingency				\$24,455	\$1,140	\$0	\$21,171	\$0	\$0	\$46,767
	<b>-- TotalWBS 9102.1.30</b>		<b>5,466</b>		<b>\$330,145</b>	<b>\$15,391</b>		<b>\$285,814</b>	<b>\$0</b>	<b>\$0</b>	<b>\$631,351</b>
	Subtotal				\$176,786	\$8,242	\$0	\$145,760	\$0	\$0	\$330,788
	Sales Tax				\$0	\$0	\$0	\$7,288	\$0	\$0	\$7,288
	INEEL Org Labor/Subcontractor Overheads				\$121,739	\$5,675	\$0	\$105,392	\$0	\$0	\$232,807
	Escalation				\$7,165	\$334	\$0	\$6,203	\$0	\$0	\$13,701
	Contingency				\$24,455	\$1,140	\$0	\$21,171	\$0	\$0	\$46,767
	<b>- Total</b>		<b>5,466</b>		<b>\$330,145</b>	<b>\$15,391</b>		<b>\$285,814</b>	<b>\$0</b>	<b>\$0</b>	<b>\$631,351</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
..	CBA6709										
..	WBS 9102.1.20										
	60 mill HDPE	U.C. per sf 364,400.00	0.004 1,458	CN-LABR \$31.58	0.126 \$46,031		0 \$0	0.3 \$109,320	0 \$0	0 \$0	0.426 \$155,351
	Subtotal WBS 9102.1.20				\$46,031		\$0	\$109,320	\$0	\$0	\$155,351
	Sales Tax				\$0		\$0	\$5,466	\$0	\$0	\$5,466
	INEEL Org Labor/Subcontractor Overheads				\$31,698		\$0	\$79,044	\$0	\$0	\$110,742
	Escalation				\$1,865		\$0	\$4,652	\$0	\$0	\$6,517
	Contingency				\$6,368		\$0	\$15,879	\$0	\$0	\$22,246
	<b>-- Total WBS 9102.1.20</b>		<b>1,458</b>		<b>\$85,962</b>		<b>\$0</b>	<b>\$214,361</b>	<b>\$0</b>	<b>\$0</b>	<b>\$300,323</b>
	Subtotal CBA6709				\$46,031		\$0	\$109,320	\$0	\$0	\$155,351
	Sales Tax				\$0		\$0	\$5,466	\$0	\$0	\$5,466
	INEEL Org Labor/Subcontractor Overheads				\$31,698		\$0	\$79,044	\$0	\$0	\$110,742
	Escalation				\$1,865		\$0	\$4,652	\$0	\$0	\$6,517
	Contingency				\$6,368		\$0	\$15,879	\$0	\$0	\$22,246
	<b>- Total CBA6709</b>		<b>1,458</b>		<b>\$85,962</b>		<b>\$0</b>	<b>\$214,361</b>	<b>\$0</b>	<b>\$0</b>	<b>\$300,323</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
. CBA6710											
-- WBS 9102.1.25											
16 oz Geotex		U.C. per sf 364,400.00	0.004 1,458	CN-LABR \$31.58	0.126 \$46,031		0 \$0	0.16 \$58,304	0 \$0	0 \$0	0.286 \$104,335
Subtotal	WBS 9102.1.25				\$46,031		\$0	\$58,304	\$0	\$0	\$104,335
Sales Tax					\$0		\$0	\$2,915	\$0	\$0	\$2,915
INEEL Org Labor/Subcontractor Overheads					\$31,698		\$0	\$42,157	\$0	\$0	\$73,855
Escalation					\$1,865		\$0	\$2,481	\$0	\$0	\$4,347
Contingency					\$6,368		\$0	\$8,469	\$0	\$0	\$14,836
<b>-- Total</b>	<b>WBS 9102.1.25</b>		<b>1,458</b>		<b>\$85,962</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,326</b>	<b>\$0</b>	<b>\$0</b>	<b>\$200,288</b>
Subtotal	CBA6710				\$46,031		\$0	\$58,304	\$0	\$0	\$104,335
Sales Tax					\$0		\$0	\$2,915	\$0	\$0	\$2,915
INEEL Org Labor/Subcontractor Overheads					\$31,698		\$0	\$42,157	\$0	\$0	\$73,855
Escalation					\$1,865		\$0	\$2,481	\$0	\$0	\$4,347
Contingency					\$6,368		\$0	\$8,469	\$0	\$0	\$14,836
<b>- Total</b>	<b>CBA6710</b>		<b>1,458</b>		<b>\$85,962</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,326</b>	<b>\$0</b>	<b>\$0</b>	<b>\$200,288</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

DIA CUSTOM GROUPING REPORT 2T

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const/Equip	Matl	S/C	Other	TOTAL*
--	CBA6712									
--	WBS 9102.1.10									
	DIRT	U.C. per hr	1	00E0912	0	65.87	0	0	0	65.87
	Grader	120.00	120		\$0	\$7,904	\$0	\$0	\$0	\$7,904
	DIRT	U.C. per hr	1	00E0612	0	101.35	0	0	0	101.35
	Cat 825 Sheepsfoot	120.00	120		\$0	\$12,162	\$0	\$0	\$0	\$12,162
	DIRT	U.C. per hr	1	00E2052	0	126.77	0	0	0	126.77
	10000 gal Water Wagon	120.00	120		\$0	\$15,212	\$0	\$0	\$0	\$15,212
	DIRT	U.C. per hr	4	CN-EQMD	139	0	0	0	0	139
	Operators & Grade Checker	120.00	480		\$16,680	\$0	\$0	\$0	\$0	\$16,680
	DIRT	U.C. per hr	2	CN-LABR	63.16	0	0	0	0	63.16
	Labor	120.00	240		\$7,579	\$0	\$0	\$0	\$0	\$7,579
	Subtotal		720		\$41,125	\$59,806	\$0	\$0	\$0	\$100,931
	Sales Tax				\$24,259	\$35,279	\$0	\$0	\$0	\$59,538
	INEEL Org Labor/Subcontractor Overheads				\$0	\$0	\$0	\$0	\$0	\$0
	Escalation				\$12,927	\$18,799	\$0	\$0	\$0	\$31,726
	Contingency				\$892	\$1,298	\$0	\$0	\$0	\$2,190
					\$3,046	\$4,430	\$0	\$0	\$0	\$7,476
--	WBS 9102.1.15									
	DIRT	U.C. per tn	0		244.26	308.45	82.05	0	0	634.76
	Mix 7% Bentonite with Soil	156.00	0		\$38,105	\$48,118	\$12,800	\$0	\$0	\$99,023
	Subtotal				\$38,105	\$48,118	\$12,800	\$0	\$0	\$99,023
	Sales Tax				\$0	\$0	\$640	\$0	\$0	\$640
	INEEL Org Labor/Subcontractor Overheads				\$20,305	\$25,641	\$7,162	\$0	\$0	\$53,108
	Escalation				\$1,402	\$1,770	\$494	\$0	\$0	\$3,666
	Contingency				\$4,785	\$6,042	\$1,688	\$0	\$0	\$12,515
--	WBS 9102.1.16									
	DIRT	U.C. per cy	0		1.3	1.93	0	0	0	3.23
	Load and Haul Clay	40,400.00	0		\$52,520	\$77,972	\$0	\$0	\$0	\$130,492
	Subtotal				\$64,596	\$81,572	\$22,784	\$0	\$0	\$168,952

INEEL

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	Spread & Compact Clay	U.C. per cy 40,400.00	0		0.97 \$39,188	1.57 \$63,428	0 \$0	0 \$0	0 \$0	2.54 \$102,616
	DIRT									
	Subtotal WBS 9102.1.16				\$91,708	\$141,400	\$0	\$0	\$0	\$233,108
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$48,869	\$75,349	\$0	\$0	\$0	\$124,218
	Escalation				\$3,374	\$5,202	\$0	\$0	\$0	\$8,576
	Contingency				\$11,516	\$17,756	\$0	\$0	\$0	\$29,272
	<b>-- Total WBS 9102.1.16</b>				<b>\$155,467</b>	<b>\$239,707</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$395,174</b>
	Subtotal CBA6712				\$154,072	\$224,797	\$12,800	\$0	\$0	\$391,669
	Sales Tax				\$0	\$0	\$640	\$0	\$0	\$640
	INEEL Org Labor/Subcontractor Overheads				\$82,101	\$119,789	\$7,162	\$0	\$0	\$209,052
	Escalation				\$5,668	\$8,270	\$494	\$0	\$0	\$14,433
	Contingency				\$19,347	\$28,228	\$1,688	\$0	\$0	\$49,263
	<b>- Total CBA6712</b>		720		<b>\$261,188</b>	<b>\$381,085</b>	<b>\$22,784</b>	<b>\$0</b>	<b>\$0</b>	<b>\$665,057</b>

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
-	CBA6714									
--	WBS 9102.1.45									
	Spread Drain Rock	U.C. per cy 6,400.00	0		2.48 \$15,872	0.55 \$3,520	15 \$96,000	0 \$0	0 \$0	18.03 \$115,392
	DIRT									
	Subtotal WBS 9102.1.45				\$15,872	\$3,520	\$96,000	\$0	\$0	\$115,392
	Sales Tax				\$0	\$0	\$4,800	\$0	\$0	\$4,800
	INEEL Org Labor/Subcontractor Overheads				\$8,458	\$1,876	\$53,714	\$0	\$0	\$64,047
	Escalation				\$584	\$129	\$3,708	\$0	\$0	\$4,422
	Contingency				\$1,993	\$442	\$12,658	\$0	\$0	\$15,093
	<b>-- Total WBS 9102.1.45</b>				<b>\$26,907</b>	<b>\$5,967</b>	<b>\$170,880</b>	<b>\$0</b>	<b>\$0</b>	<b>\$203,754</b>
	Subtotal CBA6714				\$15,872	\$3,520	\$96,000	\$0	\$0	\$115,392
	Sales Tax				\$0	\$0	\$4,800	\$0	\$0	\$4,800
	INEEL Org Labor/Subcontractor Overheads				\$8,458	\$1,876	\$53,714	\$0	\$0	\$64,047
	Escalation				\$584	\$129	\$3,708	\$0	\$0	\$4,422
	Contingency				\$1,993	\$442	\$12,658	\$0	\$0	\$15,093
	<b>- Total CBA6714</b>				<b>\$26,907</b>	<b>\$5,967</b>	<b>\$170,880</b>	<b>\$0</b>	<b>\$0</b>	<b>\$203,754</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const/Equip</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
-	CBA6716									
--	WBS 9115.1.01									
8" HDPE	PIPE	U.C. per lf 1,200.00	0.15 180	CN-PIPE \$39.33	5.9 \$7,079	0 \$0	4.55 \$5,460	0 \$0	0 \$0	10.45 \$12,539
16 HDPE	PIPE	U.C. per lf 800.00	0.25 200	CN-PIPE \$39.33	9.833 \$7,866	0 \$0	15.65 \$12,520	0 \$0	0 \$0	25.483 \$20,386
16" Tee	PIPE	U.C. per ea 6.00	3 18	CN-PIPE \$39.33	117.99 \$708	0 \$0	475 \$2,850	0 \$0	0 \$0	592.99 \$3,558
HDPE Machine	PIPE	U.C. per mo 2.00	0		0 \$0	5000 \$10,000	0 \$0	0 \$0	0 \$0	5000 \$10,000
Subtotal	WBS 9115.1.01				\$15,653	\$10,000	\$20,830	\$0	\$0	\$46,483
Sales Tax					\$0	\$0	\$1,042	\$0	\$0	\$1,042
INEEL Org Labor/Subcontractor Overheads					\$9,385	\$5,995	\$13,112	\$0	\$0	\$28,492
Escalation					\$601	\$384	\$840	\$0	\$0	\$1,824
Contingency					\$2,051	\$1,310	\$2,866	\$0	\$0	\$6,227
<b>-- Total</b>	<b>WBS 9115.1.01</b>		<b>398</b>		<b>\$27,690</b>	<b>\$17,689</b>	<b>\$38,689</b>	<b>\$0</b>	<b>\$0</b>	<b>\$84,069</b>
Subtotal	CBA6716				\$15,653	\$10,000	\$20,830	\$0	\$0	\$46,483
Sales Tax					\$0	\$0	\$1,042	\$0	\$0	\$1,042
INEEL Org Labor/Subcontractor Overheads					\$9,385	\$5,995	\$13,112	\$0	\$0	\$28,492
Escalation					\$601	\$384	\$840	\$0	\$0	\$1,824
Contingency					\$2,051	\$1,310	\$2,866	\$0	\$0	\$6,227
<b>- Total</b>	<b>CBA6716</b>		<b>398</b>		<b>\$27,690</b>	<b>\$17,689</b>	<b>\$38,689</b>	<b>\$0</b>	<b>\$0</b>	<b>\$84,069</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

DIA CUSTOM GROUPING REPORT 2T

Client: D. K. Vernon  
 Prepared By: J. C. Grenz  
 Estimate Type: Project Support

Project Name:  
 ICD Phase II  
 Project Location: INTEC  
 Estimate Number: 2448-D

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const/Equip	Matl	S/C	Other	TOTAL*
--	CBA6717									
--	WBS 9102.1.50									
	16 oz Geotex	U.C. per sf 364,400.00	0.004 1,458	ON-LABR \$31.58	0.126 \$46,031	0 \$0	0.16 \$58,304	0 \$0	0 \$0	0.286 \$104,335
	Subtotal WBS 9102.1.50				\$46,031	\$0	\$58,304	\$0	\$0	\$104,335
	Sales Tax				\$0	\$0	\$2,915	\$0	\$0	\$2,915
	INEEL Org Labor/Subcontractor Overheads				\$31,698	\$0	\$42,157	\$0	\$0	\$73,855
	Escalation				\$1,865	\$0	\$2,481	\$0	\$0	\$4,347
	Contingency				\$6,368	\$0	\$8,469	\$0	\$0	\$14,836
--	Total WBS 9102.1.50		1,458		\$85,962	\$0	\$114,326	\$0	\$0	\$200,288
--	WBS 9102.1.55									
	DIRT	U.C. per cy 38,500.00	0		0.66 \$25,410	0.94 \$36,190	0 \$0	0 \$0	0 \$0	1.6 \$61,600
	Load and Haul Material									
	DIRT	U.C. per cy 38,500.00	0		1.01 \$38,885	1.2 \$46,200	0 \$0	0 \$0	0 \$0	2.21 \$85,085
	Spread and Compact									
	Subtotal WBS 9102.1.55				\$64,295	\$82,390	\$0	\$0	\$0	\$146,685
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$34,261	\$43,904	\$0	\$0	\$0	\$78,165
	Escalation				\$2,365	\$3,031	\$0	\$0	\$0	\$5,396
	Contingency				\$8,074	\$10,346	\$0	\$0	\$0	\$18,420
--	Total WBS 9102.1.55				\$108,995	\$139,671	\$0	\$0	\$0	\$248,666
	Subtotal CBA6717				\$110,326	\$82,390	\$58,304	\$0	\$0	\$251,020
	Sales Tax				\$0	\$0	\$2,915	\$0	\$0	\$2,915
	INEEL Org Labor/Subcontractor Overheads				\$65,959	\$43,904	\$42,157	\$0	\$0	\$152,020
	Escalation				\$4,231	\$3,031	\$2,481	\$0	\$0	\$9,743
	Contingency				\$14,441	\$10,346	\$8,469	\$0	\$0	\$33,256
-	Total CBA6717		1,458		\$194,957	\$139,671	\$114,326	\$0	\$0	\$448,954

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	WBS 9102.1.03									
	Subtotal				\$348	\$287	\$0	\$0	\$0	\$634
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$185	\$153	\$0	\$0	\$0	\$338
	Escalation				\$13	\$11	\$0	\$0	\$0	\$23
	Contingency				\$44	\$36	\$0	\$0	\$0	\$80
	<b>-- Total WBS 9102.1.03</b>		<b>10</b>		<b>\$589</b>	<b>\$486</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,075</b>
	WBS 9103.1.01									
	Subtotal				63.16	0	0	0	0	63.16
	Sales Tax				\$632	\$0	\$0	\$0	\$0	\$632
	INEEL Org Labor/Subcontractor Overheads				8.953	1.5	0	0	0	10.453
	Escalation				\$1,835	\$308	\$0	\$0	\$0	\$2,143
	Contingency				1.305	0	0.35	0	0	1.655
	<b>-- Total WBS 9103.1.01</b>		<b>209</b>		<b>\$3,002</b>	<b>\$0</b>	<b>\$805</b>	<b>\$0</b>	<b>\$0</b>	<b>\$3,807</b>
	WBS 9109.1.01									
	Subtotal				94.74	0	80	0	0	174.74
	Sales Tax				\$2,179	\$0	\$1,840	\$0	\$0	\$4,019
	INEEL Org Labor/Subcontractor Overheads				\$7,647	\$308	\$2,645	\$0	\$0	\$10,600
	Escalation				\$0	\$0	\$132	\$0	\$0	\$132
	Contingency				\$4,292	\$173	\$1,559	\$0	\$0	\$6,024
	<b>-- Total WBS 9109.1.01</b>		<b>6</b>		<b>\$12</b>	<b>\$59</b>	<b>\$533</b>	<b>\$0</b>	<b>\$0</b>	<b>\$402</b>
	special coating									
	Subtotal				0.79	0	0.8	0	0	1.59
	Sales Tax				\$182	\$0	\$184	\$0	\$0	\$366
	INEEL Org Labor/Subcontractor Overheads				0.025	0	0	0	0	0.025
	Escalation				\$31.59	\$0	\$0	\$0	\$0	\$31.59
	Contingency				230.00	\$0	\$0	\$0	\$0	\$230.00
	<b>-- Total WBS 9109.1.01</b>		<b>6</b>		<b>\$31.59</b>	<b>\$0</b>	<b>\$184</b>	<b>\$0</b>	<b>\$0</b>	<b>\$366</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const	Eqp	Matl	S/C	Other	TOTAL*
	Subtotal WBS 9109.1.01				\$182		\$0	\$184	\$0	\$0	\$366
	Sales Tax				\$0		\$0	\$9	\$0	\$0	\$9
	INEEL Org Labor/Subcontractor Overheads				\$102		\$0	\$108	\$0	\$0	\$210
	Escalation				\$7		\$0	\$7	\$0	\$0	\$14
	Contingency				\$44		\$0	\$46	\$0	\$0	\$90
	<b>-- Total WBS 9109.1.01</b>		<b>6</b>		<b>\$334</b>		<b>\$0</b>	<b>\$355</b>	<b>\$0</b>	<b>\$0</b>	<b>\$689</b>
	<b>-- WBS 9113.01</b>										
	STEEL										
	Metal Building	U.C. per sf	0.4	CN-IRON	17.4	0	0	30	0	0	47.4
		210.00	84	\$43.50	\$3,654	\$0	\$0	\$6,300	\$0	\$0	\$9,954
	Subtotal WBS 9113.01				\$3,654		\$0	\$6,300	\$0	\$0	\$9,954
	Sales Tax				\$0		\$0	\$315	\$0	\$0	\$315
	INEEL Org Labor/Subcontractor Overheads				\$1,947		\$0	\$3,525	\$0	\$0	\$5,472
	Escalation				\$134		\$0	\$243	\$0	\$0	\$378
	Contingency				\$860		\$0	\$1,558	\$0	\$0	\$2,418
	<b>-- Total WBS 9113.01</b>		<b>84</b>		<b>\$6,596</b>		<b>\$0</b>	<b>\$11,941</b>	<b>\$0</b>	<b>\$0</b>	<b>\$18,537</b>
	<b>-- WBS 9115.1.02</b>										
	PIPE										
	4" Pipe/Fittings	U.C. per ea	1	CN-PIPE	39.33	0	0	15.9	0	0	55.23
		150.00	150	\$39.33	\$5,900	\$0	\$0	\$2,385	\$0	\$0	\$8,285
	4" Ball Valve	U.C. per ea	3	CN-PIPE	117.99	0	0	700	0	0	817.99
		4.00	12	\$39.33	\$472	\$0	\$0	\$2,800	\$0	\$0	\$3,272
	4" Flow Meter	U.C. per ea	5	CN-PIPE	196.65	0	0	1720	0	0	1916.65
		3.00	15	\$39.33	\$590	\$0	\$0	\$5,160	\$0	\$0	\$5,750
	Flow Totalizer	U.C. per ea	2	CN-PIPE	78.66	0	0	500	0	0	578.66
		3.00	6	\$39.33	\$236	\$0	\$0	\$1,500	\$0	\$0	\$1,736
	4" Vac Relief Valve	U.C. per ea	8	CN-PIPE	314.64	0	0	2000	0	0	2314.64
		6.00	48	\$39.33	\$1,888	\$0	\$0	\$12,000	\$0	\$0	\$13,888
	4" Butterfly Valve	U.C. per ea	3	CN-PIPE	117.99	0	0	400	0	0	517.99
		1.00	3	\$39.33	\$118	\$0	\$0	\$400	\$0	\$0	\$518
	4" Check Valve	U.C. per ea	3	CN-PIPE	117.99	0	0	660	0	0	777.99
		3.00	9	\$39.33	\$354	\$0	\$0	\$1,980	\$0	\$0	\$2,334
	1/2" Ball Valve	U.C. per ea	2	CN-PIPE	78.66	0	0	40	0	0	118.66
		4.00	8	\$39.33	\$315	\$0	\$0	\$160	\$0	\$0	\$475

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

DIA CUSTOM GROUPING REPORT 2T

Client: D. K. Vernon  
 Prepared By: J. C. Grenz  
 Estimate Type: Project Support

Project Name:  
**ICDF Phase II**  
 Project Location: INTEC  
 Estimate Number: 2448-D

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const Eqp	Matl	S/C	Other	TOTAL*
	PIPE	U.C. per ea								
4" Subersable Pump		3.00	20	CN-PIPE	786.6	0	5000	0	0	5786.6
			60	\$39.33	\$2,360	\$0	\$15,000	\$0	\$0	\$17,360
Subtotal	WBS 9115.1.02				\$12,232	\$0	\$41,385	\$0	\$0	\$53,617
Sales Tax					\$0	\$0	\$2,069	\$0	\$0	\$2,069
INEEL Org Labor/Subcontractor Overheads					\$7,333	\$0	\$26,052	\$0	\$0	\$33,385
Escalation					\$470	\$0	\$1,668	\$0	\$0	\$2,138
Contingency					\$1,603	\$0	\$5,694	\$0	\$0	\$7,297
<b>-- Total WBS 9115.1.02</b>			<b>311</b>		<b>\$21,637</b>	<b>\$0</b>	<b>\$76,868</b>	<b>\$0</b>	<b>\$0</b>	<b>\$98,505</b>
<b>-- WBS 9116.1.01</b>										
ELEC		U.C. per Ea	12	CN-ELEC	430.68	0	4500	0	0	4930.68
Motor Control Center, MCC-Tx, 1 section		1.00	12	\$35.89	\$431	\$0	\$4,500	\$0	\$0	\$4,931
ELEC		U.C. per Ea	3	CN-ELEC	107.67	0	780	0	0	887.67
15 KVA Transformer, 480/108-120		1.00	3	\$35.89	\$108	\$0	\$780	\$0	\$0	\$888
ELEC		U.C. per Ea	3	CN-ELEC	107.67	0	750	0	0	857.67
100 amp Lighting panel		1.00	3	\$35.89	\$108	\$0	\$750	\$0	\$0	\$858
ELEC		U.C. per Ea	1	CN-ELEC	35.89	0	300	0	0	335.89
Secondary pump level controller		2.00	2	\$35.89	\$72	\$0	\$600	\$0	\$0	\$672
ELEC		U.C. per Ea	1	CN-ELEC	35.89	0	286	0	0	321.89
30 amp Nema 1 disconnect		3.00	3	\$35.89	\$108	\$0	\$858	\$0	\$0	\$966
ELEC		U.C. per Ea	4	CN-ELEC	143.56	0	2500	0	0	2643.56
Pump control panel		1.00	4	\$35.89	\$144	\$0	\$2,500	\$0	\$0	\$2,644
Subtotal	WBS 9116.1.01				\$969	\$0	\$9,988	\$0	\$0	\$10,957
Sales Tax					\$0	\$0	\$499	\$0	\$0	\$499
INEEL Org Labor/Subcontractor Overheads					\$516	\$0	\$5,588	\$0	\$0	\$6,105
Escalation					\$36	\$0	\$386	\$0	\$0	\$421
Contingency					\$183	\$0	\$1,975	\$0	\$0	\$2,158
<b>-- Total WBS 9116.1.01</b>			<b>27</b>		<b>\$1,704</b>	<b>\$0</b>	<b>\$18,437</b>	<b>\$0</b>	<b>\$0</b>	<b>\$20,141</b>
<b>-- WBS 9116.1.02</b>										
ELEC		U.C. per Ea	0.75	CN-ELEC	26.918	0	125	0	0	151.918
100 watt HID Wall Pack		1.00	1	\$35.89	\$27	\$0	\$125	\$0	\$0	\$152

INEEL

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	ELEC	U.C. per Ea		CN-ELEC						
	Assume interior light, 2 lamp 4" wrap around	2.00	0.75	\$35.89	26.918	\$0	75	0	0	101.918
			2		\$54		\$150	\$0	\$0	\$204
Subtotal	WBS 9116.1.02				\$81	\$0	\$275	\$0	\$0	\$356
	Sales Tax				\$0	\$0	\$14	\$0	\$0	\$14
	INEEL Org Labor/Subcontractor Overheads				\$43	\$0	\$154	\$0	\$0	\$197
	Escalation				\$3	\$0	\$11	\$0	\$0	\$14
	Contingency				\$15	\$0	\$54	\$0	\$0	\$70
<b>-- TotalWBS 9116.1.02</b>			<b>2</b>		<b>\$142</b>	<b>\$0</b>	<b>\$508</b>	<b>\$0</b>	<b>\$0</b>	<b>\$650</b>
<b>-- WBS 9116.1.04</b>										
	ELEC	U.C. per Lf	0.008	CN-ELEC	0.287	0	1.25	0	0	1.537
	1" conduit with fittings and supports	70.00	1	\$35.89	\$20	\$0	\$88	\$0	\$0	\$108
	ELEC	U.C. per Lf	0.007	CN-ELEC	0.251	0	0.8	0	0	1.051
	3/4" conduit with fittings and supports	150.00	1	\$35.89	\$38	\$0	\$120	\$0	\$0	\$158
	ELEC	U.C. per Ls	4	CN-ELEC	143.56	0	150	0	0	293.56
	Control wiring	1.00	4	\$35.89	\$144	\$0	\$150	\$0	\$0	\$294
	ELEC	U.C. per Lf	0.01	CN-ELEC	0.359	0	0.2	0	0	0.559
	2/c #16 wire	100.00	1	\$35.89	\$36	\$0	\$20	\$0	\$0	\$56
	ELEC	U.C. per Lf	0.01	CN-ELEC	0.359	0	0.25	0	0	0.609
	2/c #16 shielded wire	150.00	2	\$35.89	\$54	\$0	\$38	\$0	\$0	\$91
	ELEC	U.C. per Lf	0.007	CN-ELEC	0.251	0	0.05	0	0	0.301
	#14 wire	250.00	2	\$35.89	\$63	\$0	\$13	\$0	\$0	\$75
	ELEC	U.C. per Lf	0.008	CN-ELEC	0.287	0	0.06	0	0	0.347
	#12 wire	750.00	6	\$35.89	\$215	\$0	\$45	\$0	\$0	\$260
	Misc. Junction boxes	1.00	4	CN-ELEC	143.56	0	125	0	0	268.56
		1.00	4	\$35.89	\$144	\$0	\$125	\$0	\$0	\$269
	ELEC	U.C. per Ls	1	CN-ELEC	35.89	0	50	0	0	85.89
	Conduit and wire labels	1.00	1	\$35.89	\$36	\$0	\$50	\$0	\$0	\$86
Subtotal	WBS 9116.1.04				\$749	\$0	\$648	\$0	\$0	\$1,396
	Sales Tax				\$0	\$0	\$32	\$0	\$0	\$32
	INEEL Org Labor/Subcontractor Overheads				\$399	\$0	\$362	\$0	\$0	\$761
	Escalation				\$28	\$0	\$25	\$0	\$0	\$53
	Contingency				\$141	\$0	\$128	\$0	\$0	\$269
<b>-- TotalWBS 9116.1.04</b>			<b>21</b>		<b>\$1,316</b>	<b>\$0</b>	<b>\$1,195</b>	<b>\$0</b>	<b>\$0</b>	<b>\$2,511</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	<b>WBS 9116.1.05</b>									
	ELEC	U.C. per Ls	8	CN-ELEC	287.12	0	0	0	0	287.12
	Testing of systems and equipmnt	1.00	8	\$35.89	\$287	\$0	\$0	\$0	\$0	\$287
	Subtotal				\$287	\$0	\$0	\$0	\$0	\$287
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$153	\$0	\$0	\$0	\$0	\$153
	Escalation				\$11	\$0	\$0	\$0	\$0	\$11
	Contingency				\$54	\$0	\$0	\$0	\$0	\$54
--	<b>Total WBS 9116.1.05</b>		<b>8</b>		<b>\$505</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$505</b>
--	<b>WBS 91160.1.03</b>									
	ELEC	U.C. per Ea	1	CN-ELEC	35.89	0	575	0	0	610.89
	1/2 HP Exhaust fan	1.00	1	\$35.89	\$36	\$0	\$575	\$0	\$0	\$611
	ELEC	U.C. per Ea	1.5	CN-ELEC	53.835	0	229	0	0	282.835
	3 kW Unit Heater	1.00	2	\$35.89	\$54	\$0	\$229	\$0	\$0	\$283
	Subtotal				\$90	\$0	\$804	\$0	\$0	\$894
	Sales Tax				\$0	\$0	\$40	\$0	\$0	\$40
	INEEL Org Labor/Subcontractor Overheads				\$48	\$0	\$450	\$0	\$0	\$498
	Escalation				\$3	\$0	\$31	\$0	\$0	\$34
	Contingency				\$17	\$0	\$159	\$0	\$0	\$176
--	<b>Total WBS 91160.1.03</b>		<b>3</b>		<b>\$158</b>	<b>\$0</b>	<b>\$1,484</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,642</b>
	Subtotal				\$26,237	\$594	\$62,229	\$0	\$0	\$89,060
	Sales Tax				\$0	\$0	\$3,111	\$0	\$0	\$3,111
	INEEL Org Labor/Subcontractor Overheads				\$15,019	\$325	\$37,799	\$0	\$0	\$53,143
	Escalation				\$990	\$22	\$2,475	\$0	\$0	\$3,488
	Contingency				\$4,427	\$95	\$10,147	\$0	\$0	\$14,670
-	<b>Total CBA6718</b>		<b>681</b>		<b>\$46,673</b>	<b>\$1,037</b>	<b>\$115,761</b>	<b>\$0</b>	<b>\$0</b>	<b>\$163,472</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
-	CBA6723									
--	WBS 9102.2.15									
	60 mill HDPE	U.C. per sf 138,400.00	0.004 554	CN-LABR \$31.58	0.126 \$17,483	0 \$0	0.3 \$41,520	0 \$0	0 \$0	0.426 \$59,003
	Subtotal				\$17,483	\$0	\$41,520	\$0	\$0	\$59,003
	Sales Tax				\$0	\$0	\$2,076	\$0	\$0	\$2,076
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$30,021	\$0	\$0	\$42,060
	Escalation				\$709	\$0	\$1,767	\$0	\$0	\$2,475
	Contingency				\$2,418	\$0	\$6,031	\$0	\$0	\$8,449
	<b>-- Total/WBS 9102.2.15</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$81,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,063</b>
	Subtotal				\$17,483	\$0	\$41,520	\$0	\$0	\$59,003
	Sales Tax				\$0	\$0	\$2,076	\$0	\$0	\$2,076
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$30,021	\$0	\$0	\$42,060
	Escalation				\$709	\$0	\$1,767	\$0	\$0	\$2,475
	Contingency				\$2,418	\$0	\$6,031	\$0	\$0	\$8,449
	<b>- Total CBA6723</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$81,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,063</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6724									
--	WBS 9102.2.20									
	LINE									
	16 oz Geotex	U.C. per sf 138,400.00	0.004 554	CN-LABR \$31.58	0.126 \$17,483	0 \$0	0.16 \$22,144	0 \$0	0 \$0	0.286 \$39,627
	Subtotal				\$17,483	\$0	\$22,144	\$0	\$0	\$39,627
	Sales Tax				\$0	\$0	\$1,107	\$0	\$0	\$1,107
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$16,011	\$0	\$0	\$28,050
	Escalation				\$709	\$0	\$942	\$0	\$0	\$1,651
	Contingency				\$2,418	\$0	\$3,216	\$0	\$0	\$5,635
--	<b>Total WBS 9102.2.20</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$43,421</b>	<b>\$0</b>	<b>\$0</b>	<b>\$76,070</b>
--	WBS 9102.2.30									
	LINE									
	16 oz Geotex	U.C. per sf 138,400.00	0.004 554	CN-LABR \$31.58	0.126 \$17,483	0 \$0	0.16 \$22,144	0 \$0	0 \$0	0.286 \$39,627
	Subtotal				\$17,483	\$0	\$22,144	\$0	\$0	\$39,627
	Sales Tax				\$0	\$0	\$1,107	\$0	\$0	\$1,107
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$16,011	\$0	\$0	\$28,050
	Escalation				\$709	\$0	\$942	\$0	\$0	\$1,651
	Contingency				\$2,418	\$0	\$3,216	\$0	\$0	\$5,635
--	<b>Total WBS 9102.2.30</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$43,421</b>	<b>\$0</b>	<b>\$0</b>	<b>\$76,070</b>
	Subtotal				\$34,965	\$0	\$44,288	\$0	\$0	\$79,253
	Sales Tax				\$0	\$0	\$2,214	\$0	\$0	\$2,214
	INEEL Org Labor/Subcontractor Overheads				\$24,078	\$0	\$32,023	\$0	\$0	\$56,101
	Escalation				\$1,417	\$0	\$1,885	\$0	\$0	\$3,302
	Contingency				\$4,837	\$0	\$6,433	\$0	\$0	\$11,270
-	<b>Total CBA6724</b>		<b>1,107</b>		<b>\$65,297</b>	<b>\$0</b>	<b>\$86,842</b>	<b>\$0</b>	<b>\$0</b>	<b>\$152,140</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC

10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6725									
--	WBS 9102.2.01									
	Foundation Excavation	U.C. per hr 10.00	1 10	CN-EQMD \$34.75	34.75 \$348	28.68 \$287	0 \$0	0 \$0	0 \$0	63.43 \$634
	Subtotal WBS 9102.2.01				\$348	\$287	\$0	\$0	\$0	\$634
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$185	\$153	\$0	\$0	\$0	\$338
	Escalation				\$13	\$11	\$0	\$0	\$0	\$23
	Contingency				\$44	\$36	\$0	\$0	\$0	\$80
--	<b>Total WBS 9102.2.01</b>		<b>10</b>		<b>\$589</b>	<b>\$486</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,075</b>
--	WBS 9103.2.01									
	Fine Grade	U.C. per hr 10.00	2 20	CN-LABR \$31.58	63.16 \$632	0 \$0	0 \$0	0 \$0	0 \$0	63.16 \$632
	Form Foundation	U.C. per sf 205.00	0.25 51	CN-CARP \$35.81	8.953 \$1,835	1.5 \$308	0 \$0	0 \$0	0 \$0	10.453 \$2,143
	Place Rebar	U.C. per lb 2,300.00	0.03 69	CN-IRON \$43.50	1.305 \$3,002	0 \$0	0.35 \$805	0 \$0	0 \$0	1.655 \$3,807
	Place, Finish & Cure Conc	U.C. per cy 23.00	3 69	CN-LABR \$31.58	94.74 \$2,179	0 \$0	80 \$1,840	0 \$0	0 \$0	174.74 \$4,019
	Subtotal WBS 9103.2.01				\$7,647	\$308	\$2,645	\$0	\$0	\$10,600
	Sales Tax				\$0	\$0	\$132	\$0	\$0	\$132
	INEEL Org Labor/Subcontractor Overheads				\$4,292	\$173	\$1,559	\$0	\$0	\$6,024
	Escalation				\$287	\$12	\$104	\$0	\$0	\$402
	Contingency				\$1,467	\$59	\$533	\$0	\$0	\$2,059
--	<b>Total WBS 9103.2.01</b>		<b>209</b>		<b>\$13,693</b>	<b>\$551</b>	<b>\$4,973</b>	<b>\$0</b>	<b>\$0</b>	<b>\$19,217</b>
--	WBS 9109.2.01									
	special coating	U.C. per sf 230.00	0.025 6	CN-PORD \$31.59	0.79 \$182	0 \$0	0.8 \$184	0 \$0	0 \$0	1.59 \$366

**INEEL**  
 \*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Project Name:  
**ICDF Phase II**  
Project Location: **INTEC**  
Estimate Number: **2448-D**

Client: **D. K. Vernon**  
Prepared By: **J. C. Grenz**  
Estimate Type: **Project Support**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const/Eqp	Matl	S/C	Other	TOTAL*
	Subtotal WBS 9109.2.01				\$182	\$0	\$184	\$0	\$0	\$366
	Sales Tax				\$0	\$0	\$9	\$0	\$0	\$9
	INEEL Org Labor/Subcontractor Overheads				\$102	\$0	\$108	\$0	\$0	\$210
	Escalation				\$7	\$0	\$7	\$0	\$0	\$14
	Contingency				\$44	\$0	\$46	\$0	\$0	\$90
	<b>-- Total WBS 9109.2.01</b>		<b>6</b>		<b>\$334</b>	<b>\$0</b>	<b>\$355</b>	<b>\$0</b>	<b>\$0</b>	<b>\$689</b>
	<b>-- WBS 9113.2.01</b>									
	STEEL		0.4	CN-IRON	17.4	0	30	0	0	47.4
	Metal Building		84	\$43.50	\$3,654	\$0	\$6,300	\$0	\$0	\$9,954
	Subtotal WBS 9113.2.01				\$3,654	\$0	\$6,300	\$0	\$0	\$9,954
	Sales Tax				\$0	\$0	\$315	\$0	\$0	\$315
	INEEL Org Labor/Subcontractor Overheads				\$1,947	\$0	\$3,525	\$0	\$0	\$5,472
	Escalation				\$134	\$0	\$243	\$0	\$0	\$378
	Contingency				\$860	\$0	\$1,558	\$0	\$0	\$2,418
	<b>-- Total WBS 9113.2.01</b>		<b>84</b>		<b>\$6,596</b>	<b>\$0</b>	<b>\$11,941</b>	<b>\$0</b>	<b>\$0</b>	<b>\$18,537</b>
	<b>-- WBS 9115.2.01</b>									
	PIPE		1	CN-PIPE	39.33	0	15.9	0	0	55.23
	4" Pipe/Fittings		100	\$39.33	\$3,933	\$0	\$1,590	\$0	\$0	\$5,523
	PIPE		3	CN-PIPE	117.99	0	700	0	0	817.99
	4" Ball Valve		6	\$39.33	\$236	\$0	\$1,400	\$0	\$0	\$1,636
	PIPE		3	CN-PIPE	117.99	0	400	0	0	517.99
	4" Butterfly Valve		9	\$39.33	\$354	\$0	\$1,200	\$0	\$0	\$1,554
	PIPE		3	CN-PIPE	117.99	0	275	0	0	392.99
	2" Butterfly Valve		6	\$39.33	\$236	\$0	\$550	\$0	\$0	\$786
	Subtotal WBS 9115.2.01				\$4,759	\$0	\$4,740	\$0	\$0	\$9,499
	Sales Tax				\$0	\$0	\$237	\$0	\$0	\$237
	INEEL Org Labor/Subcontractor Overheads				\$2,853	\$0	\$2,984	\$0	\$0	\$5,837
	Escalation				\$183	\$0	\$191	\$0	\$0	\$374
	Contingency				\$624	\$0	\$652	\$0	\$0	\$1,276
	<b>-- Total WBS 9115.2.01</b>		<b>121</b>		<b>\$8,418</b>	<b>\$0</b>	<b>\$8,804</b>	<b>\$0</b>	<b>\$0</b>	<b>\$17,222</b>
	<b>-- WBS 9116.2.01</b>									
	ELEC		12	CN-ELEC	430.68	0	4500	0	0	4930.68
	Motor Control Center, MCC-TX, 1 section		12	\$35.89	\$431	\$0	\$4,500	\$0	\$0	\$4,931

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	ELEC	U.C. per Ea		CN-ELEC	107.67	0	780	0	0	887.67
15 KVA Transformer, 480/108-120		1.00	3	\$35.89	\$108	\$0	\$780	\$0	\$0	\$888
100 amp Lighting panel	ELEC	U.C. per Ea	3	CN-ELEC	107.67	0	750	0	0	857.67
		1.00	3	\$35.89	\$108	\$0	\$750	\$0	\$0	\$858
Secondary pump level controller	ELEC	U.C. per Ea	1	CN-ELEC	35.89	0	300	0	0	335.89
		2.00	2	\$35.89	\$72	\$0	\$600	\$0	\$0	\$672
30 amp Nema 1 disconnect	ELEC	U.C. per Ea	1	CN-ELEC	35.89	0	286	0	0	321.89
		3.00	3	\$35.89	\$108	\$0	\$858	\$0	\$0	\$966
Pump control panel	ELEC	U.C. per Ea	4	CN-ELEC	143.56	0	2500	0	0	2643.56
		1.00	4	\$35.89	\$144	\$0	\$2,500	\$0	\$0	\$2,644
Subtotal	WBS 9116.2.01				\$969	\$0	\$9,988	\$0	\$0	\$10,957
Sales Tax					\$0	\$0	\$499	\$0	\$0	\$499
INEEL Org Labor/Subcontractor Overheads					\$516	\$0	\$5,588	\$0	\$0	\$6,105
Escalation					\$36	\$0	\$386	\$0	\$0	\$421
Contingency					\$183	\$0	\$1,975	\$0	\$0	\$2,158
<b>-- Total WBS 9116.2.01</b>			<b>27</b>		<b>\$1,704</b>	<b>\$0</b>	<b>\$18,437</b>	<b>\$0</b>	<b>\$0</b>	<b>\$20,141</b>
<b>-- WBS 9116.2.02</b>	ELEC	U.C. per Ea	0.75	CN-ELEC	26,918	0	125	0	0	151,918
100 watt HID Wall Pack		1.00	1	\$35.89	\$27	\$0	\$125	\$0	\$0	\$152
Assume interior light, 2 lamp 4' wrap around	ELEC	U.C. per Ea	0.75	CN-ELEC	26,918	0	75	0	0	101,918
		2.00	2	\$35.89	\$54	\$0	\$150	\$0	\$0	\$204
Subtotal	WBS 9116.2.02				\$81	\$0	\$275	\$0	\$0	\$356
Sales Tax					\$0	\$0	\$14	\$0	\$0	\$14
INEEL Org Labor/Subcontractor Overheads					\$43	\$0	\$154	\$0	\$0	\$197
Escalation					\$3	\$0	\$11	\$0	\$0	\$14
Contingency					\$15	\$0	\$54	\$0	\$0	\$70
<b>-- Total WBS 9116.2.02</b>			<b>2</b>		<b>\$142</b>	<b>\$0</b>	<b>\$508</b>	<b>\$0</b>	<b>\$0</b>	<b>\$650</b>
<b>-- WBS 9116.2.04</b>	ELEC	U.C. per Lf	0.008	CN-ELEC	0.287	0	1.25	0	0	1.537
1" conduit with fittings and supports		70.00	1	\$35.89	\$20	\$0	\$88	\$0	\$0	\$108
3/4" conduit with fittings and supports	ELEC	U.C. per Lf	0.007	CN-ELEC	0.251	0	0.8	0	0	1.051
		150.00	1	\$35.89	\$38	\$0	\$120	\$0	\$0	\$158
Control wiring	ELEC	U.C. per Ls	4	CN-ELEC	143.56	0	150	0	0	293.56
		1.00	4	\$35.89	\$144	\$0	\$150	\$0	\$0	\$294

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC

10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name: **ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const	Egp	Matl	S/C	Other	TOTAL*
2/c #16 wire	ELEC	U.C. per Lf 100.00	0.01 1	CN-ELEC \$35.89	0.359 \$36	0	\$0	0.2 \$20	0	\$0	0.569 \$56
2/c #16 shielded wire	ELEC	U.C. per Lf 150.00	0.01 2	CN-ELEC \$35.89	0.359 \$54	0	\$0	0.25 \$38	0	\$0	0.609 \$91
#14 wire	ELEC	U.C. per Lf 250.00	0.007 2	CN-ELEC \$35.89	0.251 \$63	0	\$0	0.05 \$13	0	\$0	0.301 \$75
#12 wire	ELEC	U.C. per Lf 750.00	0.008 6	CN-ELEC \$35.89	0.287 \$215	0	\$0	0.06 \$45	0	\$0	0.347 \$260
Misc. Junction boxes	ELEC	U.C. per Ls 1.00	4 4	CN-ELEC \$35.89	143.56 \$144	0	\$0	125 \$125	0	\$0	268.56 \$269
Conduit and wire labels	ELEC	U.C. per Ls 1.00	1 1	CN-ELEC \$35.89	35.89 \$36	0	\$0	50 \$50	0	\$0	85.89 \$86
<hr/>											
Subtotal	WBS 9116.2.04		21		\$749	\$0	\$0	\$648	\$0	\$0	\$1,396
Sales Tax					\$0	\$0	\$0	\$32	\$0	\$0	\$32
INEEL Org Labor/Subcontractor Overheads					\$399	\$0	\$0	\$362	\$0	\$0	\$761
Escalation					\$28	\$0	\$0	\$25	\$0	\$0	\$53
Contingency					\$141	\$0	\$0	\$128	\$0	\$0	\$269
<b>-- Total WBS 9116.2.04</b>			<b>21</b>		<b>\$1,316</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,195</b>	<b>\$0</b>	<b>\$0</b>	<b>\$2,511</b>
<hr/>											
-- WBS 9116.2.05	ELEC	U.C. per Ls 1.00	8 8	CN-ELEC \$35.89	287.12 \$287	0	\$0	0	0	0	287.12 \$287
Testing of systems and equipmnt											
<hr/>											
Subtotal	WBS 9116.2.05				\$287	\$0	\$0	\$0	\$0	\$0	\$287
Sales Tax					\$0	\$0	\$0	\$0	\$0	\$0	\$0
INEEL Org Labor/Subcontractor Overheads					\$153	\$0	\$0	\$0	\$0	\$0	\$153
Escalation					\$11	\$0	\$0	\$0	\$0	\$0	\$11
Contingency					\$54	\$0	\$0	\$0	\$0	\$0	\$54
<b>-- Total WBS 9116.2.05</b>			<b>8</b>		<b>\$505</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$505</b>
<hr/>											
-- WBS 91160.2.03	ELEC	U.C. per Ea 1.00	1 1	CN-ELEC \$35.89	35.89 \$36	0	\$0	575	0	0	610.89 \$611
1/2 HP Exhaust fan											

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>SIC</u>	<u>Other</u>	<u>TOTAL*</u>
		U.C. per Ea								
		1.00	1.5	CN-ELEC	\$3,835	0	229	0	0	282,835
3	KW Unit Heater		2	\$35.89	\$54	\$0	\$229	\$0	\$0	\$283
Subtotal	WBS 91160.2.03				\$90	\$0	\$804	\$0	\$0	\$894
	Sales Tax				\$0	\$0	\$40	\$0	\$0	\$40
	INEEL Org Labor/Subcontractor Overheads				\$48	\$0	\$450	\$0	\$0	\$498
	Escalation				\$3	\$0	\$31	\$0	\$0	\$34
	Contingency				\$17	\$0	\$159	\$0	\$0	\$176
<b>-- Total</b>	<b>WBS 91160.2.03</b>		<b>3</b>		<b>\$158</b>	<b>\$0</b>	<b>\$1,484</b>	<b>\$0</b>	<b>\$0</b>	<b>\$1,642</b>
Subtotal	CBA6725				\$18,765	\$594	\$25,584	\$0	\$0	\$44,943
	Sales Tax				\$0	\$0	\$1,279	\$0	\$0	\$1,279
	INEEL Org Labor/Subcontractor Overheads				\$10,539	\$325	\$14,731	\$0	\$0	\$25,595
	Escalation				\$703	\$22	\$998	\$0	\$0	\$1,724
	Contingency				\$3,448	\$95	\$5,106	\$0	\$0	\$8,649
<b>- Total</b>	<b>CBA6725</b>		<b>491</b>		<b>\$33,455</b>	<b>\$1,037</b>	<b>\$47,697</b>	<b>\$0</b>	<b>\$0</b>	<b>\$82,189</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6726									
	60 mill HDPE	U.C. per sf 138,400.00	0.004 554	CN-LABR \$31.58	0.126 \$17,483	0 \$0	0.3 \$41,520	0 \$0	0 \$0	0.426 \$59,003
	Subtotal				\$17,483	\$0	\$41,520	\$0	\$0	\$59,003
	Sales Tax				\$0	\$0	\$2,076	\$0	\$0	\$2,076
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$30,021	\$0	\$0	\$42,060
	Escalation				\$709	\$0	\$1,767	\$0	\$0	\$2,475
	Contingency				\$2,418	\$0	\$6,031	\$0	\$0	\$8,449
--	<b>Total WBS 9102.2.35</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$81,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,063</b>
--	WBS 9102.2.40									
	60 mill HDPE	U.C. per sf 138,400.00	0.004 554	CN-LABR \$31.58	0.126 \$17,483	0 \$0	0.3 \$41,520	0 \$0	0 \$0	0.426 \$59,003
	Subtotal				\$17,483	\$0	\$41,520	\$0	\$0	\$59,003
	Sales Tax				\$0	\$0	\$2,076	\$0	\$0	\$2,076
	INEEL Org Labor/Subcontractor Overheads				\$12,039	\$0	\$30,021	\$0	\$0	\$42,060
	Escalation				\$709	\$0	\$1,767	\$0	\$0	\$2,475
	Contingency				\$2,418	\$0	\$6,031	\$0	\$0	\$8,449
--	<b>Total WBS 9102.2.40</b>		<b>554</b>		<b>\$32,649</b>	<b>\$0</b>	<b>\$81,415</b>	<b>\$0</b>	<b>\$0</b>	<b>\$114,063</b>
	Subtotal				\$34,965	\$0	\$83,040	\$0	\$0	\$118,005
	Sales Tax				\$0	\$0	\$4,152	\$0	\$0	\$4,152
	INEEL Org Labor/Subcontractor Overheads				\$24,078	\$0	\$60,042	\$0	\$0	\$84,120
	Escalation				\$1,417	\$0	\$3,534	\$0	\$0	\$4,951
	Contingency				\$4,837	\$0	\$12,061	\$0	\$0	\$16,898
-	<b>Total CBA6726</b>		<b>1,107</b>		<b>\$65,297</b>	<b>\$0</b>	<b>\$162,830</b>	<b>\$0</b>	<b>\$0</b>	<b>\$228,127</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6729									
--	WBS 9102.3.01									
	Foundation Excavation	U.C. per hr 15.00	15	CN-EOMD \$34.75	34.75 \$521	28.68 \$430	0 \$0	0 \$0	0 \$0	63.43 \$951
	Subtotal WBS 9102.3.01				\$521	\$430	\$0	\$0	\$0	\$951
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$278	\$229	\$0	\$0	\$0	\$507
	Escalation				\$19	\$16	\$0	\$0	\$0	\$35
	Contingency				\$65	\$54	\$0	\$0	\$0	\$119
--	Total WBS 9102.3.01		15		\$884	\$729	\$0	\$0	\$0	\$1,613
--	WBS 9103.3.01									
	Fine Grade	U.C. per hr 15.00	2 30	CN-LABR \$31.58	63.16 \$947	0 \$0	0 \$0	0 \$0	0 \$0	63.16 \$947
	Form Foundation	U.C. per sf 325.00	0.25 81	CN-CARP \$35.81	8.953 \$2,910	1.5 \$488	0 \$0	0 \$0	0 \$0	10.453 \$3,397
	Misc Emb Metal	U.C. per lb 60.00	0.15 9	CN-CARP \$35.81	5.372 \$322	0 \$0	3 \$180	0 \$0	0 \$0	8.372 \$502
	Place Rebar	U.C. per lb 3,600.00	0.03 108	CN-IRON \$43.50	1.305 \$4,698	0 \$0	0.35 \$1,260	0 \$0	0 \$0	1.655 \$5,958
	Place, Finish & Cure Conc	U.C. per cy 36.00	3 108	CN-LABR \$31.58	94.74 \$3,411	0 \$0	80 \$2,880	0 \$0	0 \$0	174.74 \$6,291
	Bollards	U.C. per ea 4.00	0		0 \$0	0 \$0	0 \$0	0 \$0	400 \$1,600	400 \$1,600
	Subtotal WBS 9103.3.01				\$12,288	\$488	\$4,320	\$0	\$1,600	\$18,695
	Sales Tax				\$0	\$0	\$216	\$0	\$0	\$216
	INEEL Org Labor/Subcontractor Overheads				\$6,897	\$274	\$2,546	\$0	\$160	\$9,876
	Escalation				\$460	\$18	\$170	\$0	\$42	\$691
	Contingency				\$2,357	\$94	\$870	\$0	\$216	\$3,537
--	Total WBS 9103.3.01		336		\$22,002	\$873	\$8,122	\$0	\$2,019	\$33,016
--	WBS 9105.3.01									
	Trench Grating	U.C. per sf 8.00	1 8	CN-IRON \$43.50	43.5 \$348	0 \$0	25 \$200	0 \$0	0 \$0	68.5 \$548

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const/Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	STEEL	U.C. per lb 1,800.00	0.02 36	CN-IRON \$43.50	0.87 \$1,566	0 \$0	2.5 \$4,500	0 \$0	0 \$0	3.37 \$6,066
Subtotal	WBS 9105.3.01				\$1,914	\$0	\$4,700	\$0	\$0	\$6,614
Sales Tax					\$0	\$0	\$235	\$0	\$0	\$235
INEEL Org Labor/Subcontractor Overheads					\$1,020	\$0	\$2,630	\$0	\$0	\$3,650
Escalation					\$70	\$0	\$182	\$0	\$0	\$252
Contingency					\$451	\$0	\$1,162	\$0	\$0	\$1,613
<b>-- TotalWBS 9105.3.01</b>			<b>44</b>		<b>\$3,455</b>	<b>\$0</b>	<b>\$8,908</b>	<b>\$0</b>	<b>\$0</b>	<b>\$12,363</b>
<b>-- WBS 9109.3.01</b>	CONC	U.C. per sf 960.00	0.025 24	CN-PORD \$31.59	0.79 \$758	0 \$0	0.8 \$768	0 \$0	0 \$0	1.59 \$1,526
special coating					\$758	\$0	\$768	\$0	\$0	\$1,526
Subtotal	WBS 9109.3.01				\$758	\$0	\$768	\$0	\$0	\$1,526
Sales Tax					\$0	\$0	\$38	\$0	\$0	\$38
INEEL Org Labor/Subcontractor Overheads					\$426	\$0	\$453	\$0	\$0	\$878
Escalation					\$28	\$0	\$30	\$0	\$0	\$59
Contingency					\$182	\$0	\$193	\$0	\$0	\$375
<b>-- TotalWBS 9109.3.01</b>			<b>24</b>		<b>\$1,394</b>	<b>\$0</b>	<b>\$1,483</b>	<b>\$0</b>	<b>\$0</b>	<b>\$2,877</b>
<b>-- WBS 9115.3.02</b>	PIPE	U.C. per ea 1.00	8 8	CN-PIPE \$39.33	314.64 \$315	0 \$0	28 \$28	0 \$0	0 \$0	342.64 \$343
8" Flange Adapter					\$315	\$0	\$28	\$0	\$0	\$343
8" Flange Ring		U.C. per ea 1.00	1 1	CN-PIPE \$39.33	39.33 \$39	0 \$0	15 \$15	0 \$0	0 \$0	54.33 \$54
4" Flange Adapter		U.C. per ea 1.00	0.5 1	CN-PIPE \$39.33	19.665 \$20	0 \$0	10 \$10	0 \$0	0 \$0	29.665 \$30
4" Flange Ring		U.C. per ea 1.00	1 1	CN-PIPE \$39.33	39.33 \$39	0 \$0	15 \$15	0 \$0	0 \$0	54.33 \$54

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	PIPE	U.C. per ea	40	CN-PIPE	1573.2	0	5000	0	0	6573.2
	6" Standpipe	1.00	40	\$39.33	\$1,573	\$0	\$5,000	\$0	\$0	\$6,573
Subtotal	WBS 9115.3.02				\$1,986	\$0	\$5,068	\$0	\$0	\$7,054
Sales Tax					\$0	\$0	\$253	\$0	\$0	\$253
INEEL Org Labor/Subcontractor Overheads					\$1,191	\$0	\$3,190	\$0	\$0	\$4,381
Escalation					\$76	\$0	\$204	\$0	\$0	\$281
Contingency					\$260	\$0	\$697	\$0	\$0	\$958
<b>-- Total WBS 9115.3.02</b>			<b>51</b>		<b>\$3,513</b>	<b>\$0</b>	<b>\$9,413</b>	<b>\$0</b>	<b>\$0</b>	<b>\$12,927</b>
Subtotal	CBA6729				\$17,467	\$918	\$14,856	\$0	\$1,600	\$34,841
Sales Tax					\$0	\$0	\$743	\$0	\$0	\$743
INEEL Org Labor/Subcontractor Overheads					\$9,811	\$503	\$8,819	\$0	\$160	\$19,292
Escalation					\$655	\$34	\$586	\$0	\$42	\$1,317
Contingency					\$3,316	\$148	\$2,923	\$0	\$216	\$6,602
<b>- Total CBA6729</b>			<b>470</b>		<b>\$31,248</b>	<b>\$1,602</b>	<b>\$27,926</b>	<b>\$0</b>	<b>\$2,019</b>	<b>\$62,795</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6731									
--	WBS 9102.3.02									
	DIRT	U.C. per cy 870.00	0		1.47 \$1,279	0.94 \$818	0 \$0	0 \$0	0 \$0	2.41 \$2,097
	Trench Excavation									
	DIRT	U.C. per cy 870.00	0		3.76 \$3,271	1.14 \$992	0 \$0	0 \$0	0 \$0	4.9 \$4,263
	Trench Backfill									
	Subtotal WBS 9102.3.02				\$4,550	\$1,810	\$0	\$0	\$0	\$6,360
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$2,425	\$964	\$0	\$0	\$0	\$3,389
	Escalation				\$167	\$67	\$0	\$0	\$0	\$234
	Contingency				\$571	\$227	\$0	\$0	\$0	\$799
--	<b>Total WBS 9102.3.02</b>				<b>\$7,714</b>	<b>\$3,068</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$10,781</b>
--	WBS 9103.3.02									
	CONC	U.C. per sf 2,900.00	0.2 580	CN-CARP \$35.81	7.162 \$20,770	1.5 \$4,350	0 \$0	0 \$0	0 \$0	8.662 \$25,120
	Form Elect Ductbank									
	CONC	U.C. per lb 4,900.00	0.03 147	CN-IRON \$43.50	1.305 \$6,395	0 \$0	0.35 \$1,715	0 \$0	0 \$0	1.655 \$8,110
	Place Rebar									
	CONC	U.C. per cy 82.00	2 164	CN-LABR \$31.58	63.16 \$5,179	0 \$0	80 \$6,560	0 \$0	0 \$0	143.16 \$11,739
	Place, Finish & Cure Conc									
	Subtotal WBS 9103.3.02				\$32,343	\$4,350	\$8,275	\$0	\$0	\$44,968
	Sales Tax				\$0	\$0	\$414	\$0	\$0	\$414
	INEEL Org Labor/Subcontractor Overheads				\$18,153	\$2,441	\$4,877	\$0	\$0	\$25,471
	Escalation				\$1,212	\$163	\$326	\$0	\$0	\$1,700
	Contingency				\$6,205	\$835	\$1,667	\$0	\$0	\$8,706
--	<b>Total WBS 9103.3.02</b>		<b>891</b>		<b>\$57,914</b>	<b>\$7,789</b>	<b>\$15,558</b>	<b>\$0</b>	<b>\$0</b>	<b>\$81,260</b>
--	WBS 9116.3.01									
	ELEC	U.C. per lf 2,900.00	0.2 580	CN-ELEC \$35.89	7.178 \$20,816	0 \$0	1 \$2,900	0 \$0	0 \$0	8.178 \$23,716
	Ductbank Conduit & Supports									
	ELEC	U.C. per Lf 3,000.00	0.032 96	CN-ELEC \$35.89	1.148 \$3,445	0 \$0	0.9 \$2,700	0 \$0	0 \$0	2.048 \$6,145
	3/0 wire, building feeder									
	ELEC	U.C. per Lf 1,000.00	0.016 16	CN-ELEC \$35.89	0.574 \$574	0 \$0	0.5 \$500	0 \$0	0 \$0	1.074 \$1,074
	#1 wire, ground									

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const</u>	<u>Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
	ELEC	U.C. per Ls		CN-ELEC							
Building Grounding		1.00	8	\$35.89	287.12	\$287	\$0	400	\$0	\$0	687.12
								\$400			\$687
Subtotal	WBS 9116.3.01				\$25,123	\$0	\$0	\$6,500	\$0	\$0	\$31,623
Sales Tax					\$0	\$0	\$0	\$325	\$0	\$0	\$325
INEEL Org Labor/Subcontractor Overheads					\$13,387	\$0	\$0	\$3,637	\$0	\$0	\$17,024
Escalation					\$924	\$0	\$0	\$251	\$0	\$0	\$1,175
Contingency					\$3,943	\$0	\$0	\$1,071	\$0	\$0	\$5,015
<b>-- TotalWBS 9116.3.01</b>			<b>700</b>		<b>\$43,378</b>	<b>\$0</b>	<b>\$0</b>	<b>\$11,784</b>	<b>\$0</b>	<b>\$0</b>	<b>\$55,162</b>
Subtotal	CBA6731				\$62,017	\$6,160	\$0	\$14,775	\$0	\$0	\$82,951
Sales Tax					\$0	\$0	\$0	\$739	\$0	\$0	\$739
INEEL Org Labor/Subcontractor Overheads					\$33,965	\$3,406	\$0	\$8,514	\$0	\$0	\$45,885
Escalation					\$2,304	\$230	\$0	\$577	\$0	\$0	\$3,110
Contingency					\$10,720	\$1,062	\$0	\$2,738	\$0	\$0	\$14,520
<b>- Total CBA6731</b>			<b>1.591</b>		<b>\$109,005</b>	<b>\$10,857</b>	<b>\$0</b>	<b>\$27,342</b>	<b>\$0</b>	<b>\$0</b>	<b>\$147,204</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name: **ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6733									
--	WBS 9102.3.03									
	DIRT	U.C. per cy 13,900.00	0	0.94	1.47 \$20,433	\$13,066	0 \$0	0 \$0	0 \$0	2.41 \$33,499
	Trench Excavation									
	DIRT	U.C. per cy 13,900.00	0	1.14	3.76 \$52,264	\$15,846	0 \$0	0 \$0	0 \$0	4.9 \$68,110
	Trench Backfill									
	Subtotal WBS 9102.3.03				\$72,697	\$28,912	\$0	\$0	\$0	\$101,609
	Sales Tax				\$0	\$0	\$0	\$0	\$0	\$0
	INEEL Org Labor/Subcontractor Overheads				\$38,739	\$15,407	\$0	\$0	\$0	\$54,145
	Escalation				\$2,674	\$1,064	\$0	\$0	\$0	\$3,738
	Contingency				\$9,129	\$3,631	\$0	\$0	\$0	\$12,759
	<b>-- Total WBS 9102.3.03</b>				<b>\$123,239</b>	<b>\$49,013</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$172,252</b>
--	WBS 9115.3.01									
	FP	U.C. per lf 1,200.00	0.15	CN-PIPE \$39.33	5.9 \$7,079	0 \$0	7.75 \$9,300	0 \$0	0 \$0	13.65 \$16,379
	8" Firewater Pipe		180							
	FP	U.C. per lf 2.00	10	CN-PIPE \$39.33	393.3 \$787	0 \$0	1260 \$2,520	0 \$0	0 \$0	1653.3 \$3,307
	Fire Hydrants		20							
	CONC	U.C. per ea 8.00	0		0 \$0	0 \$0	0 \$0	0 \$0	400 \$3,200	400 \$3,200
	Bollards									
	FP	U.C. per ea 1.00	0.4	CN-PIPE \$39.33	15.732 \$16	0 \$0	365 \$365	0 \$0	0 \$0	400.732 \$401
	12 x 8 Tee		0							
	FP	U.C. per ea 1.00	0.35	CN-PIPE \$39.33	13.765 \$14	0 \$0	85 \$85	0 \$0	0 \$0	98.765 \$99
	8" Ell		0							
	FP	U.C. per ea 1.00	0.4	CN-PIPE \$39.33	15.732 \$16	0 \$0	95 \$95	0 \$0	0 \$0	110.732 \$111
	8" Tee		0							
	PIPE	U.C. per lf 1,200.00	0.12	CN-PIPE \$39.33	4.72 \$5,664	0 \$0	2.7 \$3,240	0 \$0	0 \$0	7.42 \$8,904
	6" Process/Decon Pipe		144							
	PIPE	U.C. per 2a 2.00	5	CN-PIPE \$39.33	196.65 \$393	0 \$0	200 \$400	0 \$0	0 \$0	396.65 \$793
	Freeze Proof Hydrant		10							
	PIPE	U.C. per ea 2.00	0.7	CN-PIPE \$39.33	27.531 \$55	0 \$0	45 \$90	0 \$0	0 \$0	72.531 \$145
	4" Flange Adapter		1							
	PIPE	U.C. per ea 2.00	1	CN-PIPE \$39.33	39.33 \$79	0 \$0	15 \$30	0 \$0	0 \$0	54.33 \$109
	4" Flange Ring		2							

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name: **ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
6" Ell	PIPE	U.C. per lf 1.00	0.6 1	CN-PIPE \$39.33	23.598 \$24	0 \$0	67 \$67	0 \$0	0 \$0	90.598 \$91
6" Tee	PIPE	U.C. per lf 1.00	0.7 1	CN-PIPE \$39.33	27.531 \$28	0 \$0	75 \$75	0 \$0	0 \$0	102.531 \$103
2" w/4" Waste Water from SSSIF	PIPE	U.C. per lf 800.00	0.12 96	CN-PIPE \$39.33	4.72 \$3,776	0 \$0	2.8 \$2,240	0 \$0	0 \$0	7.52 \$6,016
4" w/ 8" Waste Water From ICDF	PIPE	U.C. per lf 1,200.00	0.15 180	CN-PIPE \$39.33	5.9 \$7,079	0 \$0	7.45 \$8,940	0 \$0	0 \$0	13.35 \$16,019
16" Flange Adapter	PIPE	U.C. per ea 6.00	10 60	CN-PIPE \$39.33	393.3 \$2,360	0 \$0	45 \$270	0 \$0	0 \$0	438.3 \$2,630
16" Flange Ring	PIPE	U.C. per ea 6.00	1 6	CN-PIPE \$39.33	39.33 \$236	0 \$0	180 \$1,080	0 \$0	0 \$0	219.33 \$1,316
10" Flange Adapter	PIPE	U.C. per ea 6.00	0.7 4	CN-PIPE \$39.33	27.531 \$165	0 \$0	50 \$300	0 \$0	0 \$0	77.531 \$465
10" Flange Ring	PIPE	U.C. per ea 6.00	1 6	CN-PIPE \$39.33	39.33 \$236	0 \$0	55 \$330	0 \$0	0 \$0	94.33 \$566
8" Flange Adapter	PIPE	U.C. per ea 16.00	8 128	CN-PIPE \$39.33	314.64 \$5,034	0 \$0	28 \$448	0 \$0	0 \$0	342.64 \$5,482
8" Flange Ring	PIPE	U.C. per ea 16.00	1 16	CN-PIPE \$39.33	39.33 \$629	0 \$0	15 \$240	0 \$0	0 \$0	54.33 \$869
4" Flange Adapter	PIPE	U.C. per ea 10.00	0.5 5	CN-PIPE \$39.33	19.665 \$197	0 \$0	10 \$100	0 \$0	0 \$0	29.665 \$297
4" Flange Ring	PIPE	U.C. per ea 10.00	1 10	CN-PIPE \$39.33	39.33 \$393	0 \$0	15 \$150	0 \$0	0 \$0	54.33 \$543
8" Tee	PIPE	U.C. per ea 2.00	2 4	CN-PIPE \$39.33	78.66 \$157	0 \$0	124 \$248	0 \$0	0 \$0	202.66 \$405
4" Tee	PIPE	U.C. per ea 1.00	1.5 2	CN-PIPE \$39.33	58.995 \$59	0 \$0	17 \$17	0 \$0	0 \$0	75.995 \$76
8" Ell	PIPE	U.C. per ea 1.00	1.5 2	CN-PIPE \$39.33	58.995 \$59	0 \$0	120 \$120	0 \$0	0 \$0	178.995 \$179
4" Ell	PIPE	U.C. per ea 1.00	1 1	CN-PIPE \$39.33	39.33 \$39	0 \$0	14 \$14	0 \$0	0 \$0	53.33 \$53

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
		U.C. per mo								
		1.00	0		\$0	\$5,000	\$0	\$0	\$0	\$5,000
HDPE Machine	PIPE									
Subtotal	WBS 9115.3.01				\$34,573	\$5,000	\$30,784	\$0	\$3,200	\$73,557
Sales Tax					\$0	\$0	\$1,539	\$0	\$0	\$1,539
INEEL Org Labor/Subcontractor Overheads					\$21,413	\$2,998	\$20,505	\$0	\$320	\$45,236
Escalation					\$1,344	\$192	\$1,268	\$0	\$84	\$2,888
Contingency					\$4,586	\$655	\$4,328	\$0	\$288	\$9,868
<b>-- TotalWBS 9115.3.01</b>			<b>879</b>		<b>\$61,916</b>	<b>\$8,845</b>	<b>\$58,424</b>	<b>\$0</b>	<b>\$3,893</b>	<b>\$133,077</b>
Subtotal	CBA6733				\$107,270	\$33,912	\$30,784	\$0	\$3,200	\$175,166
Sales Tax					\$0	\$0	\$1,539	\$0	\$0	\$1,539
INEEL Org Labor/Subcontractor Overheads					\$60,151	\$18,404	\$20,505	\$0	\$320	\$99,381
Escalation					\$4,018	\$1,256	\$1,268	\$0	\$84	\$6,626
Contingency					\$13,715	\$4,286	\$4,328	\$0	\$288	\$22,617
<b>- Total CBA6733</b>			<b>879</b>		<b>\$185,155</b>	<b>\$57,857</b>	<b>\$58,424</b>	<b>\$0</b>	<b>\$3,893</b>	<b>\$305,329</b>

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const/Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	CBA6734									
--	WBS 9102.3.04									
6"	Sub Base	U.C. per cy 1,100.00	0		0.97 \$1,067	1.57 \$1,727	20 \$22,000	0 \$0	0 \$0	22.54 \$24,794
4"	AC	U.C. per ln 1,350.00	0		0 \$0	0 \$0	0 \$0	80 \$108,000	0 \$0	80 \$108,000
Subtotal	WBS 9102.3.04				\$1,067	\$1,727	\$22,000	\$108,000	\$0	\$132,794
Sales Tax					\$0	\$0	\$1,100	\$0	\$0	\$1,100
INEEL Org Labor/Subcontractor Overheads					\$569	\$920	\$12,309	\$57,551	\$0	\$71,349
Escalation					\$39	\$64	\$850	\$3,973	\$0	\$4,926
Contingency					\$134	\$217	\$2,901	\$13,562	\$0	\$16,814
<b>-- Total</b>	<b>WBS 9102.3.04</b>				<b>\$1,809</b>	<b>\$2,928</b>	<b>\$39,160</b>	<b>\$183,086</b>	<b>\$0</b>	<b>\$226,982</b>
Subtotal	CBA6734				\$1,067	\$1,727	\$22,000	\$108,000	\$0	\$132,794
Sales Tax					\$0	\$0	\$1,100	\$0	\$0	\$1,100
INEEL Org Labor/Subcontractor Overheads					\$569	\$920	\$12,309	\$57,551	\$0	\$71,349
Escalation					\$39	\$64	\$850	\$3,973	\$0	\$4,926
Contingency					\$134	\$217	\$2,901	\$13,562	\$0	\$16,814
<b>- Total</b>	<b>CBA6734</b>				<b>\$1,809</b>	<b>\$2,928</b>	<b>\$39,160</b>	<b>\$183,086</b>	<b>\$0</b>	<b>\$226,982</b>

**INEEL**  
 \*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

<u>LEVEL</u>	<u>Org/Subcontractor</u>	<u>QTY</u>	<u>Hrs</u>	<u>Crew/Rate</u>	<u>Labor</u>	<u>Const/Eqp</u>	<u>Matl</u>	<u>S/C</u>	<u>Other</u>	<u>TOTAL*</u>
--	<b>CBA6735</b>									
--	<b>WBS 9102.3.05</b>									
	STEEL	U.C. per lf	0.15	CN-IRON	6.525	2.3	13	0	0	21,825
	5' high 9 ga Chin Link Fence	5,600.00	840	\$43.50	\$36,540	\$12,880	\$72,800	\$0	\$0	\$122,220
	STEEL	U.C. per lf	1	CN-IRON	43.5	15	83	0	0	141.5
	18' Slide Gate	18.00	18	\$43.50	\$783	\$270	\$1,494	\$0	\$0	\$2,547
	STEEL	U.C. per ea	12	CN-IRON	522	200	350	0	0	1072
	20' Double Swing Gate	1.00	12	\$43.50	\$522	\$200	\$350	\$0	\$0	\$1,072
	STEEL	U.C. per ea	4	CN-IRON	174	55	100	0	0	329
	4' Swing Gate	2.00	8	\$43.50	\$348	\$110	\$200	\$0	\$0	\$658
	Subtotal				\$38,193	\$13,460	\$74,844	\$0	\$0	\$126,497
	Sales Tax				\$0	\$0	\$3,742	\$0	\$0	\$3,742
	INEEL Org Labor/Subcontractor Overheads				\$20,352	\$7,173	\$41,877	\$0	\$0	\$69,401
	Escalation				\$1,405	\$495	\$2,891	\$0	\$0	\$4,791
	Contingency				\$4,796	\$1,690	\$9,868	\$0	\$0	\$16,355
--	<b>Total WBS 9102.3.05</b>		<b>878</b>		<b>\$64,746</b>	<b>\$22,818</b>	<b>\$133,222</b>	<b>\$0</b>	<b>\$0</b>	<b>\$220,787</b>
--	<b>WBS 9116.3.02</b>									
	ELEC	U.C. per ea	10	CN-ELEC	358.9	0	600	0	0	958.9
	Motor Operator	1.00	10	\$35.89	\$359	\$0	\$600	\$0	\$0	\$959
	ELEC	U.C. per lf	0.012	CN-ELEC	0.431	0.25	0	0	0	0.681
	Trenching	800.00	10	\$35.89	\$345	\$200	\$0	\$0	\$0	\$545
	ELEC	U.C. per lf	0.002	CN-ELEC	0.072	0	0.9	0	0	0.972
	Ground Wire	800.00	2	\$35.89	\$57	\$0	\$720	\$0	\$0	\$777

**INEEL**

\*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

Project Name:  
**ICDF Phase II**  
 Project Location: **INTEC**  
 Estimate Number: **2448-D**

**DIA CUSTOM GROUPING REPORT 2T**

Client: **D. K. Vernon**  
 Prepared By: **J. C. Grenz**  
 Estimate Type: **Project Support**

LEVEL	Org/Subcontractor	QTY	Hrs	Crew/Rate	Labor	Const Eqp	Matl	S/C	Other	TOTAL*
	ELEC	U.C. per ea		CN-ELEC						
Cadwelds		80.00	20	\$35.89	8,973	\$0	\$400	\$0	\$0	13,973
					\$718	\$0				\$1,118
Subtotal	WBS 9116.3.02				\$1,479	\$200				\$3,399
Sales Tax					\$0	\$0				\$86
INEEL Org Labor/Subcontractor Overheads					\$788	\$107				\$962
Escalation					\$54	\$7				\$66
Contingency					\$232	\$31				\$283
<b>-- TotalWBS 9116.3.02</b>			<b>41</b>		<b>\$2,553</b>	<b>\$345</b>	<b>\$3,118</b>	<b>\$0</b>	<b>\$0</b>	<b>\$6,017</b>
Subtotal	CBA6735				\$39,672	\$13,660	\$76,564	\$0	\$0	\$129,896
Sales Tax					\$0	\$0	\$3,828	\$0	\$0	\$3,828
INEEL Org Labor/Subcontractor Overheads					\$21,140	\$7,279	\$42,839	\$0	\$0	\$71,258
Escalation					\$1,459	\$503	\$2,958	\$0	\$0	\$4,920
Contingency					\$5,028	\$1,722	\$10,152	\$0	\$0	\$16,902
<b>- Total CBA6735</b>			<b>919</b>		<b>\$67,299</b>	<b>\$23,163</b>	<b>\$136,341</b>	<b>\$0</b>	<b>\$0</b>	<b>\$226,803</b>
Subtotal	<b>TEC (TOTAL ESTIMATED COST)</b>				\$1,143,730	\$446,138	\$1,188,041	\$108,000	\$24,800	\$2,910,708
Sales Tax					\$0	\$0	\$59,402	\$0	\$0	\$59,402
INEEL Org Labor/Subcontractor Overheads					\$703,918	\$240,602	\$798,454	\$57,551	\$2,080	\$1,802,606
Escalation					\$44,344	\$16,482	\$49,102	\$3,973	\$645	\$114,545
Contingency					\$159,089	\$58,468	\$173,075	\$13,562	\$4,928	\$409,123
<b>Total TEC (TOTAL ESTIMATED COST)</b>			<b>25,196</b>		<b>\$2,051,081</b>	<b>\$761,690</b>	<b>\$2,268,074</b>	<b>\$183,086</b>	<b>\$32,453</b>	<b>\$5,296,384</b>

**INEEL**  
 \*Note: Total Excludes PF, G&A, and OPC  
 10/16/2001

## **Appendix CC**

### **Technical and Functional Requirements—WAG 3 INEEL CERCLA Disposal Facility Landfill and Evaporation Pond**

**TFR-71**

**TO VIEW APPENDIX CC SEE:  
DOCUMENT ID NUMBER – TFR-71, REV.02**

## **Appendix DD**

# **Technical and Functional Requirements for the INEEL CERCLA Disposal Facility Control and Integrated Waste Tracking System**

**TFR-2520**

**TO VIEW APPENDIX DD SEE:  
DOCUMENT ID NUMBER – TFR-2520, REV.0**